

See "Instructions for Filling out the Work Permit" contained in the Work Planning and Control for Experiments and Operations Subject Area.

1. Work request WCC fills out this section.
☐ Standing Work Permit

Requester: Don Lynch	Date: 10/21/2016	Ext.: 2253	Dept/Div/Group: PO/PHENIX
Other Contact person (if different from requester): Carter Biggs			Ext.: 7515
Work Control Coordinator: Carter Biggs		Start Date: 10/21/2016	Est. End Date: 12/1/2016
Brief Description of Work: MuTr Station 2 & 3 north and south removal and disposal			
Building: 1008	Room: IR & AH	Equipment: PHENIX MuTr Sta 2&3 N&S Detector Subsystems	Service Provider: PHENIX Techs, Engineers & Subsystem Experts, PHENIX Electrician, C-A Carpenters and Riggers

2. WCC, Requester/Designee, Service Provider, and ESSH (as necessary) fill out this section or attach analysis

ESSH ANALYSIS							
Radiation Concerns	<input type="checkbox"/> None	<input checked="" type="checkbox"/> Activation	<input type="checkbox"/> Airborne	<input type="checkbox"/> Contamination	<input type="checkbox"/> Radiation	<input type="checkbox"/> NORM	<input type="checkbox"/> Other
<input type="checkbox"/> Special nuclear materials involved, notify Isotope Special Materials Group				<input type="checkbox"/> Fissionable/Radiological materials involved, notify Laboratory Nuclear Safety Officer			
Radiation Generating Devices:	<input type="checkbox"/> Radiography		<input type="checkbox"/> Moisture Density Gauges	<input type="checkbox"/> Soil Density Gauges		<input type="checkbox"/> X-ray Equipment	
Safety and Security Concerns	<input type="checkbox"/> None		<input type="checkbox"/> Explosives	<input type="checkbox"/> Transport of Haz/Rad Material		<input type="checkbox"/> Pressurized Systems	
<input type="checkbox"/> Adding/Removing Walls or Roofs	<input type="checkbox"/> Critical Lift	<input type="checkbox"/> Fumes/Mist/Dust*	<input type="checkbox"/> Magnetic Fields*		<input type="checkbox"/> Railroad Work		
<input type="checkbox"/> Asbestos*	<input type="checkbox"/> Cryogenic	<input type="checkbox"/> Heat/Cold Stress	<input type="checkbox"/> Nanomaterials/particles*		<input checked="" type="checkbox"/> Rigging		
<input type="checkbox"/> Beryllium*	<input type="checkbox"/> Electrical	<input type="checkbox"/> Hydraulic	<input type="checkbox"/> Noise*		<input type="checkbox"/> Silica*		
<input type="checkbox"/> Biohazard*	<input checked="" type="checkbox"/> Elevated Work	<input type="checkbox"/> Lasers*	<input type="checkbox"/> Non-ionizing Radiation*		<input type="checkbox"/> Security Concerns		
<input type="checkbox"/> Chemicals/Corrosives*	<input type="checkbox"/> Excavation	<input type="checkbox"/> Lead*	<input type="checkbox"/> Oxygen Deficiency*		<input type="checkbox"/> Suspect/Counterfeit Items		
<input type="checkbox"/> Confined Space*	<input type="checkbox"/> Ergonomics*	<input type="checkbox"/> Material Handling	<input type="checkbox"/> Penetrating Fire Walls		<input type="checkbox"/> Vacuum		
Ladder Access Required: <input checked="" type="checkbox"/> Portable Ladder <input type="checkbox"/> Fixed Ladder- Status/Restrictions:							
* Safety Health Rep. Review Required		<input type="checkbox"/> Haz, Rad, Bio Material Exceed DOE 151.1-C Levels - Contact OEM				<input type="checkbox"/> Other	
Environmental Concerns			<input checked="" type="checkbox"/> None		<input type="checkbox"/> Work impacts Environmental Permit No.		
<input type="checkbox"/> Atmospheric Discharges (rad/non-rad/GHG)		<input type="checkbox"/> Land Use Institutional Controls		<input type="checkbox"/> Soil Activation/contamination		<input type="checkbox"/> Waste-Mixed	
<input type="checkbox"/> Chemical or Rad Material Storage or Use		<input type="checkbox"/> Liquid Discharges		<input type="checkbox"/> Waste-Clean		<input type="checkbox"/> Waste-Radioactive	
<input type="checkbox"/> Cesspools (UIC)		<input type="checkbox"/> PCB Management		<input type="checkbox"/> Waste-Hazardous		<input type="checkbox"/> Waste-Regulated Medical	
<input type="checkbox"/> High water/power consumption		<input type="checkbox"/> Spill potential		<input type="checkbox"/> Waste-Industrial		<input type="checkbox"/> Historical Environmental Hazards	
Waste disposition by: <input type="checkbox"/> Other							
Pollution Prevention (P2)/Waste Minimization Opportunity: <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes				Environmental Preferable Products Available: <input type="checkbox"/> No <input type="checkbox"/> Yes			
FACILITY CONCERNS		<input checked="" type="checkbox"/> None		<input type="checkbox"/> Intermittent Energy Release			
<input type="checkbox"/> Access/Egress Limitations		<input type="checkbox"/> Electrical Noise		<input type="checkbox"/> Potential to Cause a False Alarm		<input type="checkbox"/> Vibrations	
<input type="checkbox"/> Credited Controls (Use USI Process)		<input type="checkbox"/> Impacts Facility Use Agreement		<input type="checkbox"/> Temperature Change		<input type="checkbox"/> Other	
<input type="checkbox"/> Configuration Management		<input type="checkbox"/> Maintenance Work on Ventilation Systems		<input type="checkbox"/> Utility Interruptions			
WORK CONTROLS							
Work Practices							
<input type="checkbox"/> None		<input type="checkbox"/> Exhaust Ventilation		<input checked="" type="checkbox"/> Lockout/Tagout		<input type="checkbox"/> Spill Containment	
<input checked="" type="checkbox"/> Back-up Person/Watch		<input type="checkbox"/> HP Coverage		<input type="checkbox"/> Posting/Warning Signs		<input type="checkbox"/> Time Limitation	
<input type="checkbox"/> Barricades		<input type="checkbox"/> IH Survey		<input checked="" type="checkbox"/> Scaffolding-req's inspection		<input type="checkbox"/> Warning Alarm (i.e. "high level")	
						<input type="checkbox"/> Electrical Inspection Required	
Personal Protective Equipment							
<input type="checkbox"/> None		<input type="checkbox"/> Ear Plugs		<input checked="" type="checkbox"/> Gloves, as necessary		<input type="checkbox"/> Lab Coat	
<input type="checkbox"/> Coveralls		<input type="checkbox"/> Ear Muffs		<input type="checkbox"/> Goggles		<input type="checkbox"/> Respirator*	
<input type="checkbox"/> Disposable Clothing		<input type="checkbox"/> Face Shield		<input checked="" type="checkbox"/> Hard Hat, as req'd		<input type="checkbox"/> Shoe Covers	
				<input checked="" type="checkbox"/> Safety Shoes, as req'd		<input type="checkbox"/> High visibility cloths/vest	
						<input type="checkbox"/> Other	
Permits Required (Permits must be valid when job is scheduled.)							
<input checked="" type="checkbox"/> None		<input type="checkbox"/> Cutting/Welding		<input type="checkbox"/> Impair Fire Protection Systems			
<input type="checkbox"/> Concrete/Masonry Penetration		<input type="checkbox"/> Digging/Core Drilling		<input type="checkbox"/> Rad Work Permit-RWP No			
<input type="checkbox"/> Confined Space Entry		<input type="checkbox"/> Electrical Working Hot		<input type="checkbox"/> Other Confined Space 2A certification			
Dosimetry/Monitoring							
<input checked="" type="checkbox"/> None		<input type="checkbox"/> Heat Stress Monitor		<input type="checkbox"/> Real Time Monitor		<input type="checkbox"/> TLD	
<input type="checkbox"/> Air Effluent		<input type="checkbox"/> Noise Survey/Dosimeter		<input type="checkbox"/> Self-reading Pencil Dosimeter		<input type="checkbox"/> Waste Characterization	
<input type="checkbox"/> Ground Water		<input type="checkbox"/> O ₂ /Combustible Gas		<input type="checkbox"/> Self-reading Digital Dosimeter		<input type="checkbox"/> Other	
<input type="checkbox"/> Liquid Effluent		<input type="checkbox"/> Passive Vapor Monitor		<input type="checkbox"/> Sorbent Tube/Filter Pump			
Training Requirements (List specific training requirements)							
PHENIX Awareness, C-A Access, (where appropriate: Crane Operator, Fork lift Operator, Working at heights, Electrical Safety I, LOTO)							
Work screening has identified the following as the reason for permitted work:				When work is categorized as worker planned work and a permit is used only the following signatures are required: (Although allowed, there is no need to use back of form)			
<input type="checkbox"/> ESSH				WCC: _____ Date: _____			
<input type="checkbox"/> Complexity				Service Provider: _____ Date: _____			
<input type="checkbox"/> Work Coordination				Authorization to start: _____ Date: _____			
<input checked="" type="checkbox"/> Permit Not Required (Sections 3 through 7 optional)				(Department/Division, or their equivalent, Sup/WCC/Designee)			

3. Both work requester and service provider contribute to work plan (use attachments for detailed plans)

Work Plan (procedures, timing, equipment, scheduling, coordination, notifications, and personnel availability need to be addressed in adequate detail): See attached work plan and procedure

Special Working Conditions Required (e.g., Industrial Hygiene hold points or other monitoring)
None

Notifications to operations and Operational Limits Requirements: None

Post Work Testing, Notification or Documentation Required: See Attached Plan

Job Safety Analysis Required: ☐ Yes ☒ No

Review Done: ☒ in series ☐ team

Reviewed by: * Primary Reviewer signature (not required for Worker Planned Work) means that the Review Team members were appropriate for the work that was planned, the Team visited the job site, hazards and risks that could impact ESSH have been considered and controls established according to BNL requirements. In addition, this signature indicates that applicable JRAs, FRAs, as well as other planning documents have been reviewed and training requirements have been identified and recorded on this permit.

Title	Name (print)	Signature	Life #	Date
ES&H Professional				
F&O Facility Project Manager				
Service Provider				
Work Control Coordinator	Paul Giannotti			
Safety Health Representative				
Research Space Manager				
Other				
Other				
Required Walkdown Completed				
*Primary Reviewer				

4. Job site personnel (Supervisor and workers) fill out this section.

Note: Signature indicates personnel performing work have read and understand the hazards and permit requirements (including any attachments) and all training required for this permit is current/complete. Job Supervisor/Contractor Supervisor signatures also includes verification that worker training required for this permit is current/complete.

Job Supervisor:		Contractor Supervisor:	
Workers:	Life#:	Workers :	Life#:

Workers are encouraged to provide feedback on ESSH concerns or on ideas for improved job work flow. Use feedback form or space below.

5. Department/Division, or their equivalent, Line Manager or Designee

Conditions are appropriate to start work: (Permit has been reviewed, work controls are in place and site is ready for job.)

Name:	Signature:	Life#:	Date:
-------	------------	--------	-------

6. Worker provides feedback.

Worker Feedback (use attached sheets as necessary)

a) WCM/WCC: Are there any changes as a result of worker feedback? ☐ Yes ☐ No

Note: See Work Planning and Control for Experiments and Operations Subject Area section 2.6.

7. Post Job Review/Closeout: Work Control Coordinator (authorizing dept.) checks quality of completed permit and ensures the work site is left in an acceptable condition. (WCC can delegate clean up of job site to work supervisor.) The WCC ensures that the change process to update drawings, placards, postings, procedures, etc., is initiated, if necessary.

Name:	Signature:	Life#:	Date:
Comments:			

MuTr Station 2&3 (North and South)

Introduction

The Muon Tracker Station 2&3, or MuTr Sta. 2&3, are detector subsystems on both the north and the south Muon Magnets. These detectors consists of four quadrants of MuTr detectors of relatively light weight components mounted on the Inside of the North and South Muon Magnets (MMN &MMS).

The PHENIX Collaboration will remove and dispose (recycle as mixed electronic equipment) these detector subsystems during the 2016 PHENIX Removal and Repurposing (R&R) starting during the shutdown after run 16 and continuing to completion after run 17. This document describes the work plan to remove and dispose of the full complement of 2 stations (north and south) for the detector. (Note: R&R of the north detector is essentially the same as for the south. Steps described below are essentially the same for north and south.)

Access to the station 2&3 MuTr equipment will be achieved using work platforms as designed by PHENIX engineering from standard scaffolding parts and unistrut. Alternatively the work may be performed using man lifts operated by appropriately trained technicians. For more information on these work platforms refer to PHENIX Document # DRL-ECD- 2012-002” “PHENIX MMN & MMS Internal Work Platforms”. (copy attached)

1. MuTr station 2&3 (north and south) removal/re-installation procedure.

(The MuTr Station 2&3 North and South Installation procedures and the MuTr 2&3 North and south “spider” support structure installation procedures are attached to this work permit and shall be consulted and in general the procedures shall be reversed to de-install all MuTr 2&3, North and South detectors, utilities, and support structures. These procedures also contain all relevant details concerning lifting and handling fixtures and equipment required to perform these tasks.)

Prior to commencing any work inside the MMS and/or MMN the upper 5 lampshade panels and any equipment/services attached to them and/or impeding their removal shall be removed and disposed of in accordance with the work permits for each of these magnets, SDD-2016-010 and SDD-2016-022, respectively.

In general all of the work required to remove these detector components is considered worker planned work and all of the equipment removed shall be discarded in the PHENIX R&R mixed metals and electronics receptacles after passing activation check by BNL Health Physics (HP) technicians. Any equipment that does not pass HP screening shall be disposed of appropriately and in accordance with BNL policy as directed by the PHENIX R&R Coordinator.

2.0 Installation Closeout

When all work described in this work permit has been completed, the PHENIX work coordinator for this set of tasks shall collect feedback from all parties. This feedback shall include critical review of any problems encountered during R&R tasks, solutions to such problems, changes to work procedures described herein during the conduct of this work, suggestions for improvements in equipment procedures and techniques and any other information deemed useful and/or relevant by the PHENIX work control coordinator. Such information shall be appropriately disseminated to the various affected/interested parties and a copy of this information shall be attached to this work permit when it is closed out.



BROOKHAVEN NATIONAL LABORATORY

ENGINEERING CALCULATION

TITLE:

PHENIX MMN & MMS Internal Work Platforms

PREPARED BY: Don Lynch, P.E.

CHECKED BY:

Introduction

Access to all internal areas of the PHENIX Muon North Magnet (MMN) and Muon South Magnet (MMS) is required during the 2012 shutdown for the following purposes:

1. To allow MuTr experts and PHENIX technicians to perform maintenance on MuTr detector electronics, wherein certain electronics components (capacitors) whose presence is necessary and have a beneficial effect on the operation of the detector, are to be installed. This operation is referred to as MuTr clamp-on capacitors in PHENIX technical group parlance. This work will be performed in the area known as the station 3 area of the MMS and MMN. Access to this area requires elevated work platforms.
2. To allow installation of new electronic terminator boards on MuTr detector subsystem. This work will be performed in the area known as the station 2 area of the MMS and MMN. Access to this area requires elevated work platforms.
3. In addition to the above work, Muon Trigger experts require access to a number of front end electronics (FEE) components in station 3 of the MMN and station 2 of the MMS for fault isolation and repair of FEE boards. The same elevated work platforms to be used for the above 2 efforts shall be used for this work.

The work platforms to be used in the these areas are new custom designed steel unistrut framed platforms that are rigidly anchored to multiple hard mount points on the MMS and MMN

The structural design of the modified work platforms will be analyzed herein.

Requirements:

The work platforms herein described comply with BNL requirements as defined in the BNL SBMS Subject Area: **Walking and Working Surfaces**, section 6 **Using Scaffolds**, in particular with the explicit requirements therein and in the OSHA requirements set forth in **29 CFR 1910.28**, and **29 CFR 1926.452**.

It is noted here that these work platforms are not pre-engineered scaffolding and as such, the analyses provided herein pertains only to the specific use described herein and in the specific configurations described herein. Any modification to the specific design described herein requires approval by a qualified engineer.

MMS Work Platforms

Work platform design for internal use in the MMS requires a custom approach for the following reasons:

- The space inside the MMS is irregularly shaped and has multiple delicate experimental structures to be built around and is thus not suitable for conventional pre-engineered scaffolding.
- The platforms need to be modified several times during the varying tasks to be accomplished during shutdown
- The platforms need to be rigid to allow safe work in the areas which surround the delicate detector panels and magnet coils.
- The platforms need to be temporary structures that must be completely removed to restore the PHENIX magnets to their run-time configuration.

It has been determined that a custom structure built from steel unistrut beams rigidly attached the MMS steel structure provides an effective versatile, easy to erect and disassemble solution to this problem

The design load for this structure shall be 2 persons per level, 3 persons, maximum, total, at any one time. (***Note: This design load must be explicitly stated in all work permits for which these work platforms will be utilized.***) A conservative calculation of stresses within the structure can be made by assuming the entire load per platform (2 persons) is taken by the cross member at either end of the platform as a concentrated load at the center of the span. A simple beam calculation then provides the maximum bending stress in the beam. The platforms themselves are designed and rated for 2 persons, and thus do not require separate analyses. The only other significant loads to be considered are buckling loads in the vertical members. This can be conservatively calculated by assuming that the entire load is at one end of the platform and the combined load of the platforms, all persons on the platforms (3 maximum) and the vertical and horizontal members comprising the specific section of the platforms is taken by one vertical member. All beam calculations assume the beams are pinned at both ends.

The most critical calculation for a horizontal load carrying beam is then for the beam with the longest unsupported length. For the column buckling calculation, the worst case buckling load is for the longest unsupported vertical section. For conservatism we will assume that the columns are pinned at the top and bottom.

Figures 1 and 2, below, show the MMS work platform design.




Figure 1: MMS Work Platform with MMS shown




Figure 2: MMS Work Platform with MMS hidden (circles are points of attachment to the MMS)

L_{hor} = the longest horizontal section of unistrut (double unistrut) is 91 inches (before additional support column is added).

L_{ver} = the longest vertical unsupported section ((double unistrut) is 79.2 inches.

The design load for horizontal members = (2 persons + platform + 91 in double unistrut at 3.8 lbs/ft) = (600 + 50 + 28.8) = 678.8 lbs.

The design load, vert. columns = (3 persons + 2 platforms + {79.2" + 62" + 36" in double unistrut @ 3.8 lbs/ft}) = (900 + 100 + 56) = 1056 lbs

For double unistrut (P1001) 96" long channels the maximum uniform load is 1200 lbs (from unistrut catalog tables, page 24). The design safety factor used in unistrut catalogs is .66Fy and .33 Fu. For BNL systems we would normally use .5 Fy and .25 Fu as a minimum. Therefore, to be conservative, we will derate the unistrut catalog allowable to 75%, making, for example, the allowable uniform load 900 lbs for a 96" channel. For a central point load on one channel the allowable load is derated by a factor of 2 to 450 lbs. Or, since the stress is inversely related to the beam length, we find the maximum length between simple supports for a beam to be $450/678.8 * 96 = 63.6$ inches. Accordingly, we will provide columns to tie upper and lower cross beams between the end fixed columns to assure that the maximum unsupported length is less than 63.6 inches.

For Double unistrut (P1001) 84" long channels the maximum allowable column buckling load is 4970 (from unistrut catalog tables, assuming an eccentric load, page 25). Derating the table value as above, the maximum allowable buckling load for an 84" column becomes 3728. As this is well above our actual load and our maximum column height is less than 84 inches, the columns in the MMS platforms are all safe from buckling loads.

MMN Work Platforms

The logic for the analyses of the MMN work platforms is the same as for the MMS. Figures 3 and 4 illustrate the work platform design.





Figure 3: MMN Work Platform with MMS shown






Figure 4: MMN Work Platform with MMN hidden (circles are points of attachment to the MMN)

As the MMN is considerably larger than the MMS version, additional cross bracing, not included in the analysis has been added.

L_{hor} = the longest horizontal section of unistrut (double unistrut) is 115 inches.

L_{ver} = the longest vertical unsupported section ((double unistrut) is 111.5 inches.

The design load for horizontal members = (2 persons + platform + 115 in double unistrut at 3.8 lbs/ft) = (600 + 50 + 54.6) = 704.6 lbs

The design load, vert. columns = (3 persons + 3 platforms + {3*68.9"+75.6"*2+82"+90.4"+65.6"+111.5"+9*84" in double unistrut @ 3.8 lbs/ft}) = (900 + 150 + 463.4) = 1513.4 lbs

The analysis for the MMN cross beams is the same as for the MMS except that the full load top be applied is slightly greater resulting in a slightly shorter allowable maximum unsupported span: $450/704.6 * 96 = 61.3$ inches. Accordingly, we will provide columns to tie upper and lower cross beams between the end fixed columns to assure that the maximum unsupported length is less than 61.3 inches.

For Double unistrut (P1001) 120" long channels the maximum allowable column buckling load is 3610 (from unistrut catalog tables, assuming an eccentric load, page 25). Derating the table value as above, the maximum allowable buckling load for an 120" column becomes 2707. As this is well above our actual load and our maximum column height is less than 120 inches, the columns in the MMN platforms are all safe from buckling loads.

Notes on configuring the work platforms

During the 2012 shutdown the station 2/3 work platforms will need to be reconfigured several times for the specific work to be performed as follows:

- (a) Upper octants of MMN station 3 MuTr east of beam pipe, west of beampipe and above beampipe.
- (b) Upper octants of MMN station 2 MuTr east of beam pipe, west of beampipe and above beampipe.
- (c) Upper octants of MMS station 3 MuTr east of beam pipe, west of beampipe and above beampipe.
- (d) Upper octants of MMS station 2 MuTr east of beam pipe, west of beampipe and above beampipe.

Attachments

Attachment 1: Selected pages from Unistrut Metal Framing General Engineering Catalog, North American Edition No. 12, Metal Framing Manufacturers Association, December 1997



UNISTRUT®
Metal Framing


GENERAL ENGINEERING CATALOG




North American
Edition
NO. 12

■ Introduction	1-19
Unistrut Metal Framing Systems.....	4-7
Quality Assurance and R&D	8-10
Materials and Finishes	11-13
Design Fundamentals	14-15
Conversion Factors	16
Reference Tables and Guide Specification	17-19
■ 1½" Framing System	20-179
Channels and Combinations	20-67
P1000 - P3300 Channel	20-45
P4000 - P9200 & Pierced Channel	46-67
Nuts, Bolts and Hardware	68-79
General Fittings	80-127
Flat Plate & 90° Angle Fittings	80-92
Angular, "Z" & "U" & Wing Fittings	93-104
Post Bases, Brackets & Beam Clamps	105-121
Trolley, Special Application	122-127
Pipe/Conduit clamps, supports and Hangers	128-147
Electrical Accessories	148-165
Concrete Inserts	166-179
■ 1¼" Framing System	180-197
■ 1⅜" Framing System	198-217
■ Special Metals and Fiberglass	218-236
Stainless Steel & Extruded Aluminum	220-225
Fiberglass	226-236
■ Index	237-250


Featuring The Unique Weldless Connection



Strong, Fast, Economical and Adjustable




- 1** Insert the spring nut anywhere along the continuous slotted channel. The rounded nut ends permit easy insertion.




A 90° clockwise turn aligns the grooves in the nut with the inturned edges of the channel.

- 2** Fittings can be placed anywhere along the channel opening, permitting complete freedom of adjustment. The need for drilling holes is eliminated.




- 3** Insert bolt through fitting and into the spring nut. (See illustration 5 for end view showing nut in place)

Additional channel sections can now be bolted to the fitting already in place by following procedure described in steps 1-3.




4



- 5** Tightening with a wrench locks the serrated teeth of the nut into the inturned edges of the channel, to complete a strong, vise-like connection.

Serving Design Professionals for Over 60 Years

Unistrut products have been helping to build a better world since 1924. Used extensively in nuclear, industrial and commercial construction markets for over 60 years, Unistrut Metal Framing has set the standard for product design, quality and performance. The initial Unistrut concept — a simple spring nut and bolt connecting a fitting to a continuous slotted channel — has evolved into a comprehensive engineered building and support system.



Unistrut — The Original Metal Framing System


There is only one Unistrut Metal Framing System. It incorporates the innovative product improvements that our research and

development group has created to give you the most complete and flexible support system available. Backed by our worldwide network of engineering and distribution centers, Unistrut provides customers with total-resource capability.

Over 50 Unistrut Service Centers — stocking standard Unistrut components — are located in


principal cities in North America to serve you quickly and directly. Many Service Centers are equipped to design and supply drawings for any type of metal framing application and also offer fabrication and installation services.

This catalog is a comprehensive presentation of Unistrut Metal Framing components plus technical data required by design, specification and construction professionals.




The Most Complete Metal Framing System — Offering Three Channel-Width Options

Adjustability, demountability and reusability are engineered into each of the three Unistrut channel series. Each series offers channels of varying depth and gage plus a complete line of fittings and accessories.




1 5/8" width Series Channel begins on page 20.




1 5/8" (41mm) width

Designed to carry the heaviest loads and provide the widest variety of applications, the 1 5/8" series has become the accepted standard for use in mechanical, electrical and general construction applications where supports and attachments must meet the highest strength requirements.




1 1/4" width Series Channel begins on page 180.




1 1/4" (32mm) width

A framing system designed for medium loads, the 1 1/4" series is especially suitable for use in the OEM, commercial and display markets. It maintains a lightness in scale and a clean line that makes it aesthetically pleasing as well as functional.



1 3/16" width Series Channel begins on page 198.



1 3/16" (21mm) width

A unique half-size reduction of the 1 5/8" channel-width series, this smaller channel size can be used to carry light loads economically in applications such as instrumentation, retail displays and light-duty laboratory supports. It also provides the flexibility found in all Unistrut framing systems.

Framing Members

Unistrut channels and continuous inserts are accurately and carefully cold-formed to size from low carbon strip steel. One side of the channel has a continuous slot with inturned edges. Secure attachments may be made to the framing member with the use of hardened, toothed, slotted nuts which engage the inturned edges.

Raw steel shall conform to the following ASTM specifications.

GAGE	FINISH	ASTM NO.
12	GR & HG PG	A570 GR 33 A653 GR 33
14	GR & HG PG	A570 GR 33 A653 GR 33
16	GR & HG PG	A366 A653 GR 33
19	GR	A366

Fittings

Unistrut fittings, unless noted otherwise, are punch-press made from hot rolled, pickled and oiled steel plates, strip or coil, and conform to ASTM specifications A575, A576, A635 or A36. The fitting steel also meets the physical requirement of ASTM A570 GR 33. The pickling of the steel produces a smooth surface free from scale.

Nuts and Bolts

Unistrut nuts are made from steel bars. After all machining operations are complete, they are thoroughly case hardened. Nuts are rectangular with ends shaped to permit a quarter turn clockwise in the framing member

after insertion through the slotted opening in the channel. Two toothed grooves in the top of the nut engage the inturned edges of the channel and, after bolting operations are completed, will prevent any movement of the bolt and nut within the framing member. All bolts and nuts have Unified coarse screw threads. The standard framing nut is ½" and conforms to ASTM Specification A576 GR 1015 (material only). Screws conform to SAE J429 GR 2 (also meets and exceeds ASTM A307).

Finishes

PERMA-GREEN® II (GR)

Channel and parts are carefully cleaned and phosphated. Immediately after phosphating, a uniform coat of a highly effective rust-inhibiting acrylic enamel paint is applied by electro-deposition and thoroughly baked. Color is Perma-Green per Federal Standard 595a color number 14109 (dark limit V-). The resulting finish will withstand 400 hours of salt spray when tested in accordance with ASTM designation B-117.

ELECTRO-GALVANIZED (EG)

Parts, screws and nuts are coated with zinc electrolytically to commercial standards (ASTM - B633 Type III SC1).

PLAIN (PL)

Plain finish designation means that the channel retains the oiled surface applied to the raw steel during the rolling process. The fittings have the original oiled surface of the bar-stock material.

PRE-GALVANIZED (PG)

Material (steel strip) is coated with zinc by hot-dip process prior to roll-forming or press operations. The zinc coating weight is G90 conforming to ASTM Specification A653 GR 33.

HOT-DIPPED GALVANIZED (HG)

Material is coated with zinc after being roll-formed or after all manufacturing operations are completed, conforming to ASTM specification No. A123 or A153.

SPECIAL COATING

When specific applications require other than standard available finishes, special finishes can be supplied per customer requirements.

WEIGHTS AND DIMENSIONS

Weights given for all materials are approximate shipping weights. All dimensions subject to commercial tolerance within published specifications.

WE RESERVE THE RIGHT TO MAKE SPECIFICATION CHANGES WITHOUT NOTICE.

WHILE EVERY EFFORT HAS BEEN MADE TO ASSURE THE ACCURACY OF INFORMATION CONTAINED IN THIS CATALOG AT THE TIME OF PUBLICATION, WE CANNOT ACCEPT RESPONSIBILITY FOR INACCURACIES RESULTING FROM UNDETECTED ERRORS OR OMISSIONS.

THE BLUE COLOR USED ON UNISTRUT COMPONENTS ILLUSTRATED IN THIS CATALOG IS FOR GRAPHIC ENHANCEMENT ONLY, AND DOES NOT REPRESENT ACTUAL PRODUCT COLOR.


A) BEAMS

Beams are structural members loaded at right angles (perpendicular) to their length. Most beams are horizontal and subjected to gravity or vertical loads, e.g. a shelf support. However a vertical member can act as a beam under certain conditions, such as a curtain wall mullion subjected to wind loading. The bending moment developed in a beam is dependent on

- (a) the amount of load applied,
- (b) the type of loading applied, and
- (c) the support conditions.


1) Types of Beam Loading

a) Point Load



A load concentrated onto a very small length of the beam is a point load.

b) Uniform Load




A load spread evenly over a relatively long length of the beam is a uniform load.

Point and uniform loads can be placed on a beam in any combination. A series of point loads can approximate a uniform loading. The load charts and tables are based on a uniform load unless identified otherwise.


2) Support conditions

a) Simple Beam




A simple beam has supports that prevent movement left and right, or up and down, but do not restrain the beam from rotating at the supports into a natural deflected curve. Most Unistrut Metal Framing connections produce simple beams. The load charts and tables are based on simple beams unless identified otherwise.

b) Continuous Beam




Any simple beam that is supported at one or more intermediate points is a continuous beam. A mezzanine joist that passes over three or more columns is an example of a continuous beam.

c) Fixed-End Beam




Supports that prevent the beam from rotating into a natural deflected curve, produce a fixed-end beam. A welded end connection to very rigid support produces a fixed-end beam.

d) Cantilever Beam



A cantilever beam is a fixed-end beam that is supported at one end only, while the other end is unsupported. Unistrut brackets are examples of cantilever beams.

3) Deflection



All beams deflect under load. The amount of deflection is dependent on

- (a) the amount of load,
- (b) the support conditions,
- (c) the stiffness of the beam's cross-sectional shape, and
- (d) the stiffness of the beam material.

The stiffness of the beam's cross-sectional shape is measured by its "Moment Of Inertia" or "I". The larger a beam's "I", the stiffer it is and the less it will deflect. A beam's "I" can change for each major axis. The "I" of both major axes (I 1-1 and I 2-2) are provided. The stiffness of a beam's

material is measured by its "Modulus of Elasticity" or "E". The larger a material's "E", the stiffer it is and the less it deflects. For example, steel is about three times stiffer than aluminum and as a result, deflects only one-third as much. Do not confuse stiffness with strength. Two materials may have identical strengths yet still have different "E's". A high-strength aluminum may be as strong as steel and still deflect three times as much. The load charts and tables give calculated deflections for the loads shown. In many cases, a final design will be determined by the maximum deflection, not the maximum load.

4) Bending Moment

Is it strong enough? This is the final consideration for any beam. A beam must not only hold up the anticipated loads, but must also have sufficient additional capacity to safely hold unforeseen variations in applied loads and material strengths. This additional capacity is called a safety factor and is usually regulated by the various design codes and standards. A beam's strength is usually measured by an allowable bending moment or an allowable stress. The traditional approach is the allowable stress method, where a beam is determined to have a maximum allowable stress (in pounds per square inch) which is not to be exceeded. The approach of the current AISI "Specification For The Design Of Cold-Formed Steel Structural Members" is to use a maximum allowable bending moment (in inch-pounds) which is not to be exceeded. Bending moment divided by a beam's section modulus or "S" equals stress.

B) COLUMNS

Columns are structural members that are loaded parallel to their length. Most columns are vertical and are used to carry loads from a higher level to a lower level. However any member subjected to compression loads, such as a diagonal or prop brace, is a column.

A column fails by "buckling", which is a sudden loss of straightness and subsequent collapse. Allowable column load is dependent on

- (a) the length of column,
- (b) the type of loading,
- (c) the support conditions, and
- (d) the column's cross-sectional shape and material.

1) Column Length

The column length is measured from braced point to braced point. A braced point is where the column is restrained from lateral movement (translation) in all directions.

2) Types Of Column Loading

a) Concentric Loading

Loads applied to the center of gravity of the column cross-section are considered concentric. A beam that passes over and rests on the top of a column is an example of concentric loading.

b) Eccentric Loading

Any load which is not concentric is eccentric. The amount of eccentricity (in inches) has a major effect on the load-carrying capacity of any particular column. A load that is transmitted to a Unistrut Metal Framing column using a standard fitting bolted to the slot face is considered eccentric.

The load tables give allowable loads for both concentric (loaded at C.G.) and certain eccentric (loaded at slot face) loading. Allowable loads for other eccentric loading must be determined by a qualified design professional.

3) Support Conditions

Based on the support conditions, an appropriate "K" value is selected. This "K" value, which mathematically describes the column end conditions, is used in the column design equations. The most common support condition combinations are as follows:

a) Fixed Top – Fixed Bottom




Both ends are restrained against rotation and lateral movement (translation). "K" equals .65.

b) Pinned Top – Fixed Bottom




The top is restrained against lateral movement (translation) but, is allowed to rotate. The bottom is restrained against rotation and lateral movement. This is a common support condition and is used to construct the allowable column load applied at the Slot Face tables. "K" equals .80.

c) Pinned Top – Pinned Bottom



Both ends are restrained against lateral movement (translation) but, are allowed to rotate. "K" equals 1.0.

d) Fixed / Free Top – Fixed Bottom



The top is restrained against rotation but is allowed to move laterally. The bottom is restrained against rotation and lateral movement (translation). "K" equals 1.2.

4) Cross-Sectional Shape

The cross-sectional shape of a column member determines the value of its "Radius of Gyration" or "r". In general,

a member with a large "r" makes a better column than a member with a small "r". Each axis of a column has a different "r". Typically the axis with the smallest "r" determines the final design.

C) BOLT TORQUE

Bolt torque values are given to ensure the proper connection between Unistrut Metal Framing components. It is important to understand that there is a direct, but not necessarily consistent, relationship between bolt torque and tension in the bolt. Too much tension in the bolt can cause it to break or crush the component parts. Too little tension in the bolt can prevent the connection from developing its full load capacity. The torque values given have been developed over many years of experience and testing.

BOLT SIZE	1/4"	5/16"	3/8"	1/2"	5/8"	3/4"
FOOT LBS.	6	11	19	50	100	125
N·m	8	15	25	70	135	170


These are based on using a properly calibrated torque wrench with a clean dry (non-lubricated) Unistrut fitting, bolt and nut. A lubricated bolt or nut can cause extremely high tension in the connection and may lead to bolt failure. It must be noted that the accuracy of commercial torque wrenches varies widely and it is the responsibility of the installer to ensure that proper bolt torque has been achieved.

CONVERSION FACTORS



<i>To Convert From</i>	<i>To</i>	<i>Multiply By</i>	<i>To Convert From</i>	<i>Multiply To</i>	<i>By</i>
Length					
Inch [in]	Millimeter [mm]	25.400 000	Millimeter [mm]	Inch [in]	0.039 370
Foot [ft]	Meter [m]	0.304 800	Meter [m]	Foot [ft]	3.280 840
Yard [yd]	Meter [m]	0.914 400	Meter [m]	Yard [yd]	1.093 613
Mile (U.S. Statute) [mi]	Kilometer [km]	1.609 347	Kilometer [km]	Mile (U.S. Statute) [mi]	0.621 370
Area					
Square Inch [in ²]	Square Millimeter [mm ²]	645.16	Square Millimeter [mm ²]	Square Inch [in ²]	0.001550
Square Foot [ft ²]	Square Meter [m ²]	0.092 903	Square Meter [m ²]	Square Foot [ft ²]	10.763 915
Square Yard [yd ²]	Square Meter [m ²]	0.836 127	Square Meter [m ²]	Square Yard [yd ²]	1.195 991
Square Mile [mi ²] (U.S. Statute)	Square Kilometer [km ²]	2.589 998	Square Kilometer [km ²]	Square Mile [mi ²] (U.S. Statute)	0.386 101
Acre	Square Meter [m ²]	4046.873	Square Meter [m ²]	Acre	0.000 247
Acre	Hectare	0.404 687	Hectare	Acre	2.471 046
Volume					
Cubic Inch [in ³]	Cubic Millimeter [mm ³]	16387.06	Cubic Millimeter [mm ³]	Cubic Inch [in ³]	0.000061
Cubic Foot [ft ³]	Cubic Meter [m ³]	0.028 317	Cubic Meter [m ³]	Cubic Foot [ft ³]	35.314 662
Cubic Yard [yd ³]	Cubic Meter [m ³]	0.764 555	Cubic Meter [m ³]	Cubic Yard [yd ³]	1.307 950
Gallon (U.S. Liquid) [gal]	Litre [l]	3.785 412	Litre [l]	Gallon (U.S. Liquid) [gal]	0.264 172
Quart (U.S. Liquid) [qt]	Litre [l]	0.946 353	Litre [l]	Quart (U.S. Liquid) [qt]	1.056 688
Mass					
Ounce (Avoirdupois) [oz]	Gram [g]	28.349 520	Gram [g]	Ounce (Avoirdupois) [oz]	0.035 274
Pound (Avoirdupois) [lb]	Kilogram [kg]	0.453 592	Kilogram [kg]	Pound (Avoirdupois) [lb]	2.204 624
Short Ton	Kilogram [kg]	907.185	Kilogram [kg]	Short Ton	0.00110
Force					
Ounce-Force	Newton [N]	0.278 014	Newton [N]	Ounce-Force	3.596 941
Pound-Force [lbf]	Newton [N]	4.448 222	Newton [N]	Pound-Force [lbf]	0.224 809
Bending Moment					
Pound-Force-Inch [lbf-in]	Newton-Meter [N-m]	0.112 985	Newton-Meter [N-m]	Pound-Force-Inch [lbf-in]	8.850 732
Pound-Force-Foot [lbf-ft]	Newton-Meter [N-m]	1.355 818	Newton-Meter [N-m]	Pound-Force-Foot [lbf-ft]	0.737 562
Pressure, Stress					
Pound-Force per Square Inch [lbf/in ²]	Kilopascal [kPa]	6.894 757	Kilopascal [kPa]	Pound-Force per Square Inch [lbf/in ²]	0.145 038
Foot of Water (39.2 F)	Kilopascal [kPa]	2.988 980	Kilopascal [kPa]	Foot of Water (39.2 F)	0.334 562
Inch of Mercury (32 F)	Kilopascal [kPa]	3.386 380	Kilopascal [kPa]	Inch of Mercury (32 F)	0.295 301
Energy, Work, Heat					
Foot-Pound-Force [ft-lbf]	Joule [J]	1.355 818	Joule [J]	Foot-Pound-Force [ft-lbf]	0.737 562
British Thermal Unit [Btu]	Joule [J]	1055.056	Joule [J]	British Thermal Unit [Btu]	0.000948
Calorie [cal]	Joule [J]	4.186 800	Joule [J]	Calorie [cal]	0.238 846
Kilowatt Hour [kW-h]	Joule [J]	3600000	Joule [J]	Kilowatt Hour [kW-h]	2.78 ⁻⁷
Power					
Foot-Pound-Force /Second [ft-lbs/s]	Watt [W]	1.355 818	Watt [W]	Foot-Pound-Force /Second [ft-lbs/s]	0.737 562
British Thermal Unit /Hour [Btu/h]	Watt [W]	0.293 071	Watt [W]	British Thermal Unit /Hour [Btu/h]	3.412 142
Horsepower (550 Ft. Lbf/s) [hp]	Kilowatt [kW]	0.745 700	Kilowatt [kW]	Horsepower (550 Ft. Lbf/s) [hp]	1.341 022
Angle					
Degree	Radian [rad]	0.017 453	Radian [rad]	Degree	57.295 788
Temperature					
Degree Fahrenheit [F]	Degree Celsius [C]	(F° -32)/1.8	Degree Celsius [C]	Degree Fahrenheit [F]	1.8xC°+32



CANTILEVER BEAMS



$$V \text{ max.} = P$$

$$M \text{ max.} = PL$$




$$\Delta \text{ max.} = \frac{PL^3}{3EI}$$



$$V \text{ max.} = W$$

$$M \text{ max.} = \frac{WL}{2}$$


$$\Delta \text{ max.} = \frac{WL^3}{8EI}$$




$$V \text{ max.} = P$$

$$M \text{ max.} = Pb$$

$$\Delta \text{ max.} = \frac{Pb^2(3L-b)}{6EI}$$



SIMPLE BEAMS




$$R = \frac{P}{2}$$

$$V \text{ max.} = \frac{P}{2}$$

$$M \text{ max.} = \frac{PL}{4}$$

$$\Delta \text{ max.} = \frac{PL^3}{48EI}$$




$$R = \frac{W}{2}$$

$$V \text{ max.} = \frac{W}{2}$$

$$M \text{ max.} = \frac{WL}{8}$$

$$\Delta \text{ max.} = \frac{5WL^3}{384EI}$$



$$R_1 = \frac{Pb}{L}$$

$$R_2 = \frac{Pa}{L}$$


$$V \text{ max.} = \frac{Pa}{L}$$

$$M \text{ max.} = \frac{Pab}{L}$$

$$\Delta \text{ max.} = \frac{Pab(a+2b)}{27EI} \sqrt{\frac{3a(a+2b)}{L}}$$



BEAMS FIXED AT ONE END, SUPPORTED AT OTHER





$$R_1 = \frac{5P}{16}$$

$$V \text{ max.} = \frac{11P}{16}$$

$$M \text{ max.} = \frac{3PL}{16}$$

$$\Delta \text{ max. at } x = 0.447L$$

$$\Delta \text{ max.} = 0.009317 \frac{PL^3}{EI}$$






$$R_1 = \frac{3W}{8}$$

$$V \text{ max.} = \frac{5W}{8}$$

$$M \text{ max.} = \frac{WL}{8}$$

$$\Delta \text{ max. at } x = 0.4215L$$

$$\Delta \text{ max.} = \frac{WL^3}{185EI}$$





$$R_1 = \frac{Pb^2}{2L^3}(a+2L)$$


$$R_2 = \frac{Pa}{2L^3}(3L^2-a^2)$$

$$M \text{ at point of load} = R_1a$$

$$M \text{ at fixed end} = \frac{Pab}{2L^3}(a+L)$$






BEAMS FIXED AT BOTH ENDS



$$V \text{ max.} = \frac{P}{2}$$

$$M \text{ max.} = \frac{PL}{8}$$


$$\Delta \text{ max.} = \frac{PL^3}{192EI}$$



$$V \text{ max.} = \frac{W}{2}$$

$$M \text{ max.} = \frac{WL}{12}$$

$$\Delta \text{ max.} = \frac{WL^3}{384EI}$$




$$R_1 = \frac{Pb^2}{L^3}(3a+b)$$

$$R_2 = \frac{Pa^2}{L^3}(a+3b)$$

$$M_1 = \frac{Pab^2}{L^2}$$

$$M_2 = \frac{Pa^2b}{L^2}$$



R – Reaction
M – Moment
P – Concentrated Load












W – Total Uniform Load
V – Shear
L – Length

Δ – Deflection
E – Modulus of Elasticity
I – Moment of Inertia

CONVERSION FACTORS FOR BEAMS WITH VARIOUS STATIC LOADING CONDITIONS

All Beam Load tables are for single-span (simple) beams supported at the ends. These can be used in the majority of the cases.


There are times when it is necessary to know what happens with other loading and support conditions. Some common arrangements are shown below. Simply multiply the values from the Beam Load tables by factors given below

LOAD AND SUPPORT CONDITION		LOAD FACTOR	DEFLECTION FACTOR
1. Simple Beam, Uniform Load		1.00	1.00
2. Simple Beam, Concentrated Load at Center		.50	.80
3. Simple Beam, Two Equal Concentrated Loads at 1/4 pts		1.00	1.10
4. Beam Fixed at Both Ends, Uniform Load		1.50	.30
5. Beam Fixed at Both Ends, Concentrated Load at Center		1.00	.40
6. Cantilever Beam, Uniform Load		.25	2.40
7. Cantilever Beam, Concentrated Load at End		.12	3.20
8. Continuous Beam, Two Equal Spans, Uniform Load on One Span		1.30	.92
9. Continuous Beam, Two Equal Spans, Uniform Load on Both Ends		1.00	.42
10. Continuous Beam, Two Equal Spans, Concentrated Load at Center of One Span		.62	.71
11. Continuous Beam, Two Equal Spans, Concentrated Load at Center of Each Span		.67	.48

EXAMPLE I

PROBLEM:

Determine load and deflection of a P 1000 beam continuous over one support and loaded uniformly on one span.



SOLUTION:

- From load table for P1000 on page 24 load for a 5'-0" span is 680# and deflection is .35".
- Multiply by factors from Table above.
Load = 680# x 1.30 = 884#
Deflection = .35" x .92 = .32"

EXAMPLE II

PROBLEM:

Determine load and deflection of a P 5500 cantilever beam with a concentrated load on the end.



SOLUTION:

- From load table P5500 on page 57 load for a 3'-0" span is 2190# and deflection is .09".
- Multiply by factors from Table above.
Load = 2190# x .12 = 263#
Deflection = .09" x 3.20 = .29"

PART I - GENERAL

1.01 SCOPE OF WORK

- A. Provide all Unistrut Metal Framing material, fittings and related accessories (Strut System) as indicated on the Contract Drawings.
- B. Provide all labor, supervision, engineering, and fabrication required for installation of the Strut System in accordance with the Contract Drawings and as specified herein.
- C. Related work specified elsewhere.

1.02 QUALITY ASSURANCE

- A. Manufacturer's qualifications:
 - 1. The manufacturer shall not have had less than 10 year's experience in manufacturing Strut Systems.
 - 2. The manufacturer must certify in writing all components supplied have been produced in accordance with an established quality assurance program.
- B. Installer's qualifications:
 - 1. Installer must be a Unistrut trained manufacturer's authorized representative/installer with not less than 5 years experience in the installation of Strut Systems of this size and conformation.
 - 2. All Strut System components must be supplied by a single manufacturer.
- C. Standards:
 - 1. Work shall meet the requirements of the following standards.

Federal, State and Local codes.
American Iron and Steel Institute (AISI) Specification for the Design of Cold-Formed Steel Structural Members August 19, 1986 Edition, December 11, 1989 Addendum.

American Society for Testing And Materials (ASTM).

1.03 SUBMITTALS

- A. Structural Calculations and Shop Drawings
 - 1. Submit structural calculations for approval by the project engineer. Calculations may include, but are not limited to:
 - a. Description of design criteria.
 - b. Stress and deflection analysis.
 - c. Selection of Unistrut framing members, fittings, and accessories.

- 2. Submit all shop/assembly drawings necessary to completely install the Strut System in compliance with the Contract Drawings.
- 3. Submit all pertinent manufacturers published data.

1.04 PRODUCT DELIVERY, STORAGE, AND HANDLING

- A. All material is to be delivered to the work site in original factory packaging to avoid damage to the finish.
- B. Upon delivery to the work site, all components shall be protected from the elements by a shelter or other covering.

1.05 GUARANTEE

- A. Separate guarantees shall be issued from the erector and manufacturer, valid for a period of 1 year, against any defects that may arise from the installation or manufacture of the Strut System components.

PART 2 - PRODUCTS

2.01 ACCEPTABLE MANUFACTURERS

- A. All Strut System components shall be as manufactured by UNISTRUT CORPORATION or approved equal as determined by the Architect or Engineer of record in writing 10 days prior to bid date.

2.02 MATERIALS

- A. All channel members shall be fabricated from structural grade steel conforming to one of the following ASTM specifications:
A 570 GR 33, A 653 GR 33
- B. All fittings shall be fabricated from steel conforming to one of the following ASTM specifications:
A 575, A 576, A 36 or A 635
- C. Substitutions
Any substitutions of product or manufacturer must be approved in writing ten days prior to bid date, by Architect or Engineer of record.

2.03 FINISHES

- A. Strut System components shall be finished in accordance with one of the following standards:
 - 1. PERMA-GREEN® II (GR)
Rust inhibiting acrylic enamel paint applied by electro-deposition, after cleaning and phosphating, and thoroughly baked. Color is per Federal

Standard 595a color number 14109 (dark limit V-). Finish to withstand minimum 400 hours salt spray when tested in accordance with ASTM B 117.

- 2. ELECTRO-GALVANIZED (EG)
Electrolytically zinc coated per ASTM B 633 Type III SC 1
- 3. PRE-GALVANIZED (PG)
Zinc coated by hot-dipped process prior to roll forming. The zinc weight shall be G90 conforming to ASTM A 653.
- 4. HOT-DIPPED GALVANIZED (HG)
Zinc coated after all manufacturing operations are complete. Coating shall conform to ASTM A 123 or A 153.
- 5. SPECIAL COATING / MATERIAL
(Describe as applicable)

PART 3 - EXECUTION

3.01 EXAMINATION

- A. The installer shall inspect the work area prior to installation. If work area conditions are unsatisfactory, installation shall not proceed until satisfactory corrections are completed.

3.02 INSTALLATION

- A. Installation shall be accomplished by a fully trained manufacturer authorized installer.
- B. Set Strut System components into final position true to line, level and plumb, in accordance with approved shop drawings.
- C. Anchor material firmly in place. Tighten all connections to their recommended torques.

3.03 CLEANUP

- A. Upon completion of this section of work, remove all protective wraps and debris. Repair any damage due to installation of this section of work.

3.04 PROTECTION

- A. During installation, it shall be the responsibility of the installer to protect this work from damage.
- B. Upon completion of this scope of work, it shall become the responsibility of the general contractor to protect this work from damage during the remainder of construction on the project and until substantial completion.

CHANNELS & COMBINATIONS

FOR 1½" (41 MM) WIDTH SERIES CHANNEL



1½" Channels

Nuts & Hardware

General Fittings

Pipe/Conduit Supports

Electrical Fittings

Concrete Inserts

1¼" Framing System

13/16" Framing System

Spec. Metals & Fiberglass

Index

Page

P1000
12 Gage

23

P1100
14 Gage

32

P2000
16 Gage

36

P3000
12 Gage

40

P3300
12 Gage

43

P4000
16 Gage

46

P4100
14 Gage

50

P5000
12 Gage

53

P5500
12 Gage

56

Closure Strips

59

Pierced Sections

60

P9000 Series
12 Gage

62



MATERIAL

Unistrut channels are accurately and carefully cold formed to size from low-carbon strip steel.

Spot-welded combination members are welded 3" (maximum) on center.

STEEL: PLAIN

12 Ga. (2.7 mm), 14 Ga. (1.9 mm)
ASTM A570 GR 33
16 Ga. (1.5 mm) ASTM A366

STEEL: PRE-GALVANIZED

12 Ga. (2.7 mm), 14 Ga. (1.9 mm)
and 16 Ga. (1.5 mm) ASTM A653
GR 33

For other materials, see Special Metals and Fiberglass section.

FINISHES

All channels are available in: Perma Green II (GR), pre-galvanized (PG), conforming to ASTM A653; Hot-dipped galvanized (HG), conforming to ASTM A123 or A153; and plain (PL).

STANDARD LENGTHS

Standard lengths are 10 feet (3.05m) and 20 feet (6.10m). Tolerances are +⅛" (3.2 mm) to +½" (12.7 mm) to allow for cutting. Special lengths are available for a small cutting charge with a tolerance of ±⅛" (3.2mm).

CURVED CHANNEL

Many Unistrut 1½" (41mm) channel sections are available as curved pieces in both single and combination styles. Contact your local Unistrut Service Center or Unistrut Corporation for ordering information.

DIMENSIONS

Imperial dimensions are illustrated in inches. Metric dimensions are shown in millimeters and rounded to one decimal place.

LOAD DATA

All beam and column load data pertains to carbon steel and stainless steel channels. Load tables and charts are constructed to be in accordance with the SPECIFICATION FOR THE DESIGN OF COLD-FORMED STEEL STRUCTURAL MEMBERS AUGUST 19, 1986 EDITION with DECEMBER 11, 1989 ADDENDUM published by the AMERICAN IRON AND STEEL INSTITUTE.


CHANNELS & COMBINATIONS

FOR 1 5/8" (41 MM) WIDTH SERIES CHANNEL




P1000 SERIES

12 GA.
page 23




P1100 SERIES

14 GA.
page 32




P3000 SERIES

12 GA.
page 40




P2000 SERIES

16 GA.
page 36




P3300 SERIES

12 GA.
page 43




P4000 SERIES

16 GA.
page 46




P4100 SERIES

14 GA.
page 50




P5000 SERIES

12 GA.
page 53




P5500 SERIES

12 GA.
page 56



P9000 SERIES

12 GA.
page 62



See page 180 for 1-1/4" width channels and combinations and page 198 for 13/16" channels and combinations.

Combinations not shown in catalog are available on special order. Consult factory for details.

1 5/8" Channels

Nuts & Hardware

General Fittings

Pipe/Conduit Supports

Electrical Fittings

Concrete Inserts

1 1/4" Framing System

13/16" Framing System

Spec. Metals & Fiberglass










































Index

CHANNELS & COMBINATIONS

FOR 1 5/8" (41 MM) WIDTH SERIES CHANNEL



CHANNEL SELECTION CHART

Channel	Channel Dimensions				Material & Thickness			Hole Pattern Styles					
	Width		Height		Steel	Stain-less Steel	Alum.	KO	T	SL	HS	DS	H3
	In	mm	In	mm									
P1000	1 5/8	41	1 5/8	41	12 ga	12 ga	.109					 *	 *
P1100	1 5/8	41	1 5/8	41	14 ga	14 ga	—						
P2000	1 5/8	41	1 5/8	41	16 ga	—	—						
P3000	1 5/8	41	1 3/8	35	12 ga	—	—						
P3300	1 5/8	41	7/8	22	12 ga	12 ga	—						
P4000	1 5/8	41	13/16	21	16 ga	16 ga	.078						
P4100	1 5/8	41	13/16	21	14 ga	—	—						
P5000	1 5/8	41	3 1/4	83	12 ga	—	—						
P5500	1 5/8	41	2 7/16	62	12 ga	—	.109						

- This reference chart reflects the available channels and hole patterns manufactured by Unistrut Corporation.
- Stainless steel sections are also available on special order in "T," "SL" and "HS" hole pattern.
- Metric equivalent for material thickness: 12 ga. (2.7 mm); 14 ga. (1.9 mm); and 16 ga. (1.5 mm).

* Not available in aluminum.

CHANNELS & COMBINATIONS IN DESCENDING ORDER OF STRENGTH

Channel	S in ³	I in ⁴	Area in ²	Weight Lbs/Ft
P5001	1.716*	5.578*	1.794	6.10
P1004 A	1.673	4.079	1.978	6.70
P5501	1.153	2.811	1.453	4.94
P1001 C41	1.145	1.860	2.223	7.60
P5000	.628	1.099	.897	3.05
P1001	.572	.930	1.112	3.80
P1101	.456	.741	.834	2.84
P3001	.431	.593	1.007	3.40
P5500	.391	.523	.726	2.47
P2001	.379	.616	.681	2.32
P9200	.297	.278	.489	2.23

Channel	S in ³	I in ⁴	Area in ²	Weight Lbs/Ft
P9000	.203	.164	.384	2.05
P3301	.202	.177	.797	2.70
P1000	.202	.185	.556	1.90
P1100	.166	.149	.417	1.42
P3000	.154	.121	.503	1.70
P4101	.141	.114	.574	1.94
P2000	.140	.124	.340	1.16
P4001	.125	.101	.478	1.64
P3300	.072	.037	.398	1.35
P4100	.053	.025	.287	.97
P4000	.048	.023	.239	.82




* Effective section properties.

P1000® & P1001 CHANNELS

FOR 1 5/8" (41 MM) WIDTH SERIES CHANNEL






P1000



Pierced channels are found on pages 60 and 61.


Weight: 190 Lbs/C Ft (283 kg/100 m)

P1001



Weight: 380 Lbs/C Ft (566 kg/100 m)

BEAM LOAD*



*Maximum allowable uniform load.

Channel	Weight		Allowable Moment		Material Thickness		Standard Lengths		Finishes				Other Materials	
	Lbs/Ft	kg/m	In-Lb	N·m	In	mm	10'	20'	PL	GR	HG	PG	SS	EA
P1000	1.90	2.8	5,080	570	.105	2.7	■	■	■	■	■	■	■	■
P1001	3.80	5.7	14,390	1630	.105	2.7	■	■	■	■	■	■	■	■

Nominal thickness of 12 gage strip steel is .105 inches.

1 5/8" Channels

Nuts & Hardware

General Fittings

Pipe/Conduit Supports

Electrical Fittings

Concrete Inserts

1 1/4" Framing System

1 3/16" Framing System

Spec. Metals & Fiberglass

Index

P1000 & P1001 CHANNELS

FOR 1 5/8" (41 MM) WIDTH SERIES CHANNEL



BEAM LOADING DATA

Span	Channel	Max. Allowable Uniform Load		Deflection at Uniform Load		Uniform Loading at Deflections					
						Span/180		Span/240		Span/360	
In	mm	Lbs	kN	In	mm	Lbs	kN	Lbs	kN	Lbs	kN
24	610	P1000 P1001	1690 3130*	7.5 13.9	0.06 0.02	1 1	1690 3130*	7.5 13.9	1690 3130*	7.5 13.9	1690 3130*
36	914	P1000 P1001	1130 3130*	5.0 13.9	0.13 0.07	3 2	1130 3130*	5.0 13.9	1130 3130*	900 3130*	4.0 13.9
48	1219	P1000 P1001	850 2400	3.8 10.7	0.22 0.13	6 3	850 2400	3.8 10.7	760 2400	3.4 10.7	510 2400
60	1524	P1000 P1001	680 1920	3.0 8.5	0.35 0.20	9 5	650 1920	2.9 8.5	490 1920	2.2 8.5	320 1630
72	1829	P1000 P1001	560 1600	2.5 7.1	0.50 0.28	13 7	450 1600	2.0 7.1	340 1600	1.5 7.1	220 1130
84	2134	P1000 P1001	480 1370	2.1 6.1	0.68 0.39	17 10	330 1370	1.5 6.1	250 1240	1.1 5.5	170 830
96	2438	P1000 P1001	420 1200	1.9 5.3	0.89 0.50	23 13	250 1200	1.1 5.3	190 950	0.8 4.2	130 640
108	2743	P1000 P1001	380 1070	1.7 4.8	1.14 0.64	29 16	200 1000	0.9 4.4	150 750	0.7 3.3	100 500
120	3048	P1000 P1001	340 960	1.5 4.3	1.40 0.79	36 20	160 810	0.7 3.6	120 610	0.5 2.7	80 410
144	3658	P1000 P1001	280 800	1.2 3.6	1.99 1.13	51 29	110 560	0.5 2.5	80 420	0.4 1.9	60 280
168	4267	P1000 P1001	240 690	1.1 3.1	2.72 1.55	69 39	80 410	0.4 1.8	60 310	0.3 1.4	40 210
192	4877	P1000 P1001	210 600	0.9 2.7	3.55 2.02	90 51	60 320	0.3 1.4	50 240	0.2 1.1	NR 160
216	5486	P1000 P1001	190 530	0.8 2.4	4.57 2.53	116 64	50 250	0.2 1.1	40 190	0.2 0.8	NR 130
240	6096	P1000 P1001	170 480	0.8 2.1	5.61 3.15	142 80	40 200	0.2 0.9	NR 150	NR 0.7	NR 100

*Load limited by spot weld shear.

NR = Not Recommended

Notes:

1. Above loads include the weight of the member. This weight must be deducted to arrive at the net allowable load the beam will support.
2. Long span beams should be supported in such a manner as to prevent rotation and twist.
3. Allowable uniformly distributed loads are listed for various simple spans, that is, a beam on two supports. If load is concentrated at the center of the span, multiply load from the table by 0.5 and corresponding deflection by 0.8.
4. See page 66 for lateral bracing load reduction charts.

P1000 & P1001 CHANNELS

FOR 1 $\frac{5}{8}$ " (41 MM) WIDTH SERIES CHANNEL



COLUMN LOADING DATA

Unbraced Height		Channel	Max. Allowable Load at Slot Face		Maximum Column Load Applied at C.G.							
					K = .65		K = .80		K = 1.0		K = 1.2	
In	mm		Lbs	kN	Lbs	kN	Lbs	kN	Lbs	kN	Lbs	kN
24	610	P1000	3400	15.1	9600	42.7	9500	42.3	9320	41.5	9100	40.5
		P1001	6360	28.3	23820	106.0	23560	104.8	23130	102.9	22610	100.6
36	914	P1000	3000	13.3	7640	34.0	7400	32.9	7000	31.1	6490	28.9
		P1001	6190	27.5	23190	103.2	22610	100.6	21640	96.3	20460	91.0
48	1219	P1000	2570	11.4	5910	26.3	5530	24.6	4980	22.2	4430	19.7
		P1001	5970	26.6	22310	99.2	21270	94.6	19560	87.0	17460	77.7
60	1524	P1000	2230	9.9	4780	21.3	4390	19.5	3850	17.1	3330	14.8
		P1001	5690	25.3	21180	94.2	19560	87.0	16870	75.0	13590	60.5
72	1829	P1000	1970	8.8	4090	18.2	3680	16.4	3140	14.0	2650	11.8
		P1001	5360	23.8	19790	88.0	17460	77.7	13590	60.5	9570	42.6
84	2134	P1000	1760	7.8	3600	16.0	3170	14.1	2630	11.7	2160	9.6
		P1001	4970	22.1	18150	80.7	14980	66.6	10130	45.1	7030	31.3
96	2438	P1000	1580	7.0	3220	14.3	2770	12.3	2240	10.0	1800	8.0
		P1001	4510	20.1	16270	72.4	12120	53.9	7750	34.5	5380	23.9
108	2743	P1000	1430	6.4	2910	12.9	2450	10.9	1930	8.6	**	**
		P1001	4030	17.9	14120	62.8	9570	42.6	6130	27.3	4250	18.9
120	3048	P1000	1290	5.7	2640	11.7	2180	9.7	**	**	**	**
		P1001	3610	16.1	11750	52.3	7750	34.5	4960	22.1	**	**

** $\frac{KL}{r} > 200$

ELEMENTS OF SECTION

Channel	Areas of Section		Axis 1 - 1						Axis 2 - 2					
			I		S		r		I		S		r	
	In ²	cm ²	In ⁴	cm ⁴	In ³	cm ³	In	cm	In ⁴	cm ⁴	In ³	cm ³	In	cm
P1000	.556	3.6	.185	7.7	.202	3.3	.577	1.5	.236	9.8	.290	4.7	.651	1.7
P1001	1.112	7.2	.930	38.7	.572	9.4	.915	2.3	.472	19.6	.580	9.5	.651	1.7

I - Moment of Inertia

S - Section Modulus

r - Radius of Gyration

1 $\frac{5}{8}$ " Channels

Nuts & Hardware

General Fittings

Pipe/Conduit Supports

Electrical Fittings

Concrete Inserts

1 $\frac{1}{4}$ " Framing System

1 $\frac{3}{16}$ " Framing System

Spec. Metals & Fiberglass

Index



PHENIX MuTr STATION 2 SOUTH
INSTALLATION PROCEDURE

procedure name

PHENIX Procedure No. PP-2.5.5.4-10

Revision: A

Date: 6-30-00 ABB
~~4-28-00~~

Hand Processed Changes

<u>HPC No.</u>	<u>Date</u>	<u>Page Nos.</u>	<u>Initials</u>
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

Approvals

Peter Hoo 7/10/00
PHENIX S E & I Date

William S. [Signature]
Cognizant Scientist/Engineer Date
/Activity Manager

William Hoo 7/10/00
PHENIX /Safety Date

Charles Dean 7/20/00
CA-D ES&H /SAFETY Date

PHENIX Procedure # PP-2.5.5.4-10 Rev A

REVISION CONTROL SHEET

LETTER	DESCRIPTION	DATE	WRITTEN BY	APPROVED BY	CURRENT OVERSIGHT
A	First Issue	6/30/2000	n/a	P. Kroon, W. Sondheim, W. Lenz, C. Pearson	n/a
RETIRED	Installation Completed	3/20/2007	n/a	D. Lynch, P. Giannotti, R. Pisani for PHENIX	D.Lynch

Station 2 South Installation Procedure PP-2.5.5.4-10

1.0 Purpose and Scope

- 1.1 The purpose of this procedure is to provide direction for the rigging of the station 2 south octants. This procedure provides detailed instructions for the safe installation of the octants to the "spider".
Note that the weight for each octant is 250 lbs.

2.0 Responsibilities

- 2.1 All operations shall be performed under the direction of the PHENIX experimental hall "person-in-charge", or their designee.
- 2.2 Due to the delicacy of this structure, and the critical alignment of its assembly in the magnet, this procedure and all relevant BNL safety guidelines must be strictly adhered to. In accordance with BNL policy, any individual may cease operations if they in any way feel unsafe or if they believe unsafe procedures are being followed, such a complaint shall be reviewed by the cognizant engineer, and if necessary, BNL ES&H Services.
- 2.3 A representative of the muon tracking mechanical team should be present for all lifts, to consult on procedures and answer any questions as they may arise.

3.0 Prerequisites

- 3.1 Training: All personnel involved in this procedure shall have reviewed this procedure, and be fully knowledgeable about the way in which the octant is mounted in the South magnet. A meeting will take place with all participants involved with this installation to review all aspects and answer any questions that any of the personnel may have.
- 3.2 All personnel involved in this procedure shall wear hardhats and safety shoes.

4.0 Precautions

- 4.1 The area where rigging operations will be performed shall be cordoned-off to all personnel except the "person in charge" and the technicians assigned to perform this procedure.
- 4.2 Some operations will require personnel to work in close proximity to suspended loads. Do not permit anyone to be positioned under the load.
- 4.3 Lift the octants with the commercial lifting fixture only and only with the protective covers in place on the octant.

5.0 Equipment List

- 5.1 Appropriate ANVER lifting fixture, model number LBT50-MROT-SP, serial number 001764, rated load capacity 500 pounds. All four steel 5/16-18 X 2" length bolts used to attach the ANVER lifter to the four tapped holes on the octant downstream frame, as located on dwg. Number 002-0212-325 sheet D1 (see G holes) should be tightened to 150 in-lbs. PHENIX dwg no. 002-0212-610
- 5.2 "C" fixture, rated load capacity 800 pounds.
- 5.3 Guide ropes.

5.4 Shackles, rated minimum load capacity 1000 pounds.

5.5 Stainless Steel hardware, including threaded rods.

6.0 Preparation

6.1 Support "spider" in place and surveyed.

6.2 Install the stainless steel threaded rods in place on the "spider" where indicated on PHENIX drawing no. 002-0212-260, sheets D1, D2 and D3, four locations on each spoke, 32 total.

6.3 Each octant mounts to the spider in 10 locations; the 4 C holes along each side of an octant and the two middle C holes along the outer edge. These are indicated on PHENIX drawing no. 002-0212-328 sheet D1 and 002-0212-326 sheet D1. See the mounting locations on spider drawings 002-0212-260 sheets d1-d3.

6.4 Install bottom platform and side stairs as shown on magnet scaffolding assembly drawing package, Ray Savino will supply prints and hardware.

6.5 In order for the rigging crew in 1008 to become familiar with both the ANVER lifter and the "C" fixture, a non critical full scale station 2 front octant is available to practice with in the magnet.

6.6 THERE IS ONLY 1 5/8-INCH CLEARANCE BETWEEN THE CATHODE CARD CONNECTORS AND THE MAGNET LAMPSHADE PANEL. This is why using the non-critical octant in 6.5 is important.

6.7 It is critical that the brake on the crane used is in working order, lifts of a fraction of an inch may be required – and the use of a chain fall, or similar device may be required to get the fine adjustment needed to locate these chambers in the magnet.

6.8 As an added precaution, to prevent damage to the cathode readout circuit cards, install two 5/16-18 bolts that are at least two inches longer than the height of the circuit cards from the top edge of the detector frame. Screw these bolts into two of the threaded holes on the top edge of the frame. These should be removed after the octant has been secured to the support spider.

7.0 Procedure

7.1 Front octants.(smaller octants)

7.1.1 The frame side with the machined surface cutout faces are downstream, see front octant rear frame drawing 002-0212-325 sheet D1. Installation proceeds from the bottom of the spider to the top at every other location beginning with the 6:00 o'clock octant followed by the 3:00,9:00,12:00.

7.1.2 FIRST OCTANT ONLY _ 6:00 position

7.1.2.1 Attach "C" fixture to the crane hook and attach the ANVER lifting fixture to the "C" fixture.

7.1.3 Attach the ANVER lifting fixture to the octant in the horizontal position following the manufacturer instructions and with the fixtures provided. Lift the octant and tilt the octant to a vertical position.

7.1.4 Rotate the octant to the desired orientation on the "spider".

- 7.1.5 Attach guide ropes to the octant as needed.
- 7.1.6 First Octant Only
 - 7.1.6.1 Lift and lower the octant in place downstream of the spider, to allow possible rotation of the octant to get into position under the piston. Once the octant is directly under the piston move it upstream and attach to the "spider" at the outside boundary, use the threaded rods as guides on each side of the octant. Place temporary nuts and spacers on the side threaded rod. Use guide ropes to stabilize the octant. Torque the 3/8-16 stainless steel bolts and nuts to 236 in-lbs.
- 7.1.7 Remaining front octants
 - 7.1.7.1 No "C" fixture needed. Install the 3:00 and 9:00 o'clock octants next followed by the 12:00 o'clock. Lift and lower the octant into place. Attach to the spider and place temporary nuts and spacers on the threaded rod on the sides of the octants.
- 7.1.8 Remove gas window aluminum plates on the upstream side of the octants.
- 7.1.9 Install alignment lenses, 4 per octant as shown on dwgs numbered 002-0212-332 sheets D1 and D2, 002-0212-234 sheet D1, 002-0212-235 sheet D2 and 002-0212-236 sheet D6. The lens blocks that mount along the outer edge will be installed later.

7.2 Rear Octants.


- 7.2.1 The frame side with the machined surface for the lens blocks faces downstream see dwg. Number 002-0212-327 sheet D1. Installation proceeds from the bottom of the spider to the top at every other location beginning at 4:30 o'clock and proceeding in order 4:30, 7:30, 1:30, 10:30.
- 7.2.2 Attach the ANVER lifting fixture to the octant in the horizontal position following the manufacturer instructions. Lift the octant and tilt the octant to a vertical position.
- 7.2.3 Rotate the octant to the orientation in the "spider".
- 7.2.4 Attach guide ropes to the octant as needed.
- 7.2.5 Remove temporary nuts from sides of adjacent octants.
- 7.2.6 Attach 2 stabilizer brackets to the outside cross member on the spider, drawing number 002-0212-260 sheets D1 and 002-0212-261 sheet D1.
- 7.2.7 Remove protective aluminum cover on upstream side of octant.
- 7.2.8 Remove temporary nuts from threaded rods and aluminum spacer block, along spoke where octant will be attached.
- 7.2.9 Lift and lower the octant into place and attach to the stabilizer brackets at the outside boundary. Place nuts and washers on the side threaded rods and torque to 236 in-lbs.
- 7.2.10 Install alignment lenses, 4 per octant as shown on dwgs numbered 002-0212-332 sheets D1 and D2, 002-0212-234 sheets D1, 002-

0212-235 sheet D2 and 002-0212-236 sheet D6. The three lens blocks that mount along the outer edge will be attached later.



- 7.3 Remove downstream protective gas window covers from octants only after the following work has been completed; the FEE mechanical structure is in place, the lower scaffolding platform and side steps are in place, the bottom station 2 cross rib assembly is installed and connected to the chamber. It will be difficult to remove these covers later – so removal from the bottom up as the FEE cross ribs are installed is the current thinking.

8.0 Alignment

- 8.1 Alignment crew – surveys the octants from both the upstream and downstream sides, all bolts are checked for a torque of 236 in-lbs.



FAR SIDE VIEW





6-30-98 W.S.

NOTES: UNLESS OTHERWISE SPECIFIED									
1. ALL DIMENSIONS IN MILLIMETERS.									
2. DIMENSIONS ARE GIVEN PER ANSI Y14.5M-1982									
3. SURFACE TEXTURE PER ANISURF B.61-1.1985									
4. REMOVE ALL BURRS AND BREAK SHARP EDGES TO A MAXIMUM OF .38									
5. ALL INSIDE CORNERS TO BE .38 RADIIUS MAX									
6. ALL INSIDE ROUNDS TO BE .075 TO MAJOR DIAMETER									
7. COUNTERSINK 82 DEGREES APPROXIMATELY .76-.82 DEEP ALL									
8. CRITICAL HOLES									
9. PARTS TO BE THOROUGHLY CLEANED TO REMOVE ALL OIL, GREASE,									
10. PART NUMBER (DRAWING NO. PLUS DASH NO. PLUS SERIAL NO.) TO									
BE CLEARLY MARKED ON THE PART ITSELF.									
HOLE NO. REQ'D	TAPPED/MACHINED HOLE	∇	$\perp \varnothing$	∇	POSITIONAL TOLERANCING				
D	3	.190(+/-)0 - .32 U.N.F.-2B	12.70	-	$\varnothing \pm 0.30(1)$ A [B] C [D]				
K	9	(USE \varnothing 1.001 IN. REAM)	THRU	31.75 PREP FOR PIN SILE	$\varnothing \pm 0.02(3)$ A [B] C [D]				
L	6	PRESS FIT FOR \varnothing .125 IN STANDARD DOWEL PIN	15.09	-	$\varnothing \pm 0.30(1)$ A [B] C [D]				
						PARTS LIST			
						USERS OUTLINE SPECIFIED CONFORMS WITH STANDARDS			
						SECTION 8 ASME Y14.5M-1982 Y14.5M-1982 Y14.5M-1982			
						APPROVAL: 11-21-77			
						DESIGNED BY: J.E. HARRIS			
						CAN NOT GENERATE DRAWING DO NOT MANUALLY UPDATE DO NOT SCALE DRAWING			
						REVOLUTION			
						REVISED DATE			
						E. MODIANO 5-29-88			
						E. MODIANO 5-29-88			
						CHANGED 5-29-88			
						DATE 5-29-88			
						T. INDRENGER 5-29-88			
						SCALE: 1/8"			
						002-0212-328 1 of 1			
						D 1 of 1			
						A			
						PHENIX STATION 2 SOUTH- FRONT CHAMBER FRONT FRAME			
						HYTEC, INC			

[illegible]

<p>HYTEC, INC</p> <p>PHENIX STATION 2 SOUTH FRONT CHAMBER FRONT FRAME</p>		<p>DATE: 5-29-88</p> <p>BY: E. ROSENBERG</p> <p>FOR: H. MULLER</p> <p>FROM: T. HODGKINSON</p> <p>PROJECT: T. HODGKINSON</p> <p>SCALE: 1/8"</p>		<p>1 of 1</p> <p>1 of 1</p> <p>1 of 1</p>
--	--	--	--	---


8	7	6	5	4	3	2	1
---	---	---	---	---	---	---	---



SAME AS DRAWING# 002-0212-322
EXCEPT FOR AS SHOWN

U.S. AUG 03 1999

[illegible]




- Ms. B. 1. 3. 1099

[illegible]

HYTEC, INC
PHENIX STATION 2 SOUTH
SPIDER SUPPORT RING
ASSEMBLY

NO.	REV.	DESCRIPTION	DATE	BY
1	1	HYTEC 2012-260-D2-1	10/2000	HYTEC
2	1	HYTEC 2012-260-D2-1	10/2000	HYTEC
3	1	HYTEC 2012-260-D2-1	10/2000	HYTEC
4	1	HYTEC 2012-260-D2-1	10/2000	HYTEC
5	1	HYTEC 2012-260-D2-1	10/2000	HYTEC
6	1	HYTEC 2012-260-D2-1	10/2000	HYTEC
7	1	HYTEC 2012-260-D2-1	10/2000	HYTEC
8	1	HYTEC 2012-260-D2-1	10/2000	HYTEC




- NOTES: UNLESS OTHERWISE SPECIFIED
1. ALL DIMENSIONS IN MILLIMETERS
 2. SURFACE TEXTURE PER ASME Y14.5M-1994
 3. ALL DIMENSIONS TO BE .015
 4. ALL DIMENSIONS TO BE .015
 5. ALL DIMENSIONS TO BE .015
 6. ALL DIMENSIONS TO BE .015
 7. ALL DIMENSIONS TO BE .015
 8. ALL DIMENSIONS TO BE .015
 9. ALL DIMENSIONS TO BE .015

ITEM NO.	QTY.	PART NO.	DESCRIPTION
1	1	002-0212-260-D4	Upper Support Ring
2	2	002-0212-260-D10	Outer Radial Spoke
3	2	002-0212-260-D9	Central Radial Spoke
4	2	002-0212-260-D8	Rear Chamber Support
5	1	002-0212-260-D7	Front Chamber Support

HYTEC, INC
PHENIX STATION 2 SOUTH
SPIDER
TOP FRAME SUBASSEMBLY
002-0212-260 D 2

8	7	6	5	4	3	2
---	---	---	---	---	---	---





NOTE: UNLESS OTHERWISE SPECIFIED

1. ALL DIMENSIONS MILLIMETERS
2. DIMENSIONS AND TOLERANCING PER ANSI Y14.5M-1982
3. REMOVE ALL BURRS AND BREAK SHARP EDGES TO A MAXIMUM OF .38
4. ALL INSIDE CORNERS TO BE .38 RADIUS MAX
5. ALL INSIDE CORNERS TO BE .38 RADIUS MAX
6. COAT FINISHING NO. FILMS DASH NO. PLUS SERIAL NO.) TO BE CLEANLY MARKED ON THE PART ITSELF.
7. PARTS TO BE THOROUGHLY CLEANED TO REMOVE ALL OIL, GREASE, DIRT AND CHIPS
8. PARTS TO BE THOROUGHLY CLEANED TO REMOVE ALL OIL, GREASE, DIRT AND CHIPS
9. PARTS TO BE THOROUGHLY CLEANED TO REMOVE ALL OIL, GREASE, DIRT AND CHIPS

U.S. AUG 0 3 1999

8/12/99 W. S.


8	7	6	5	4	3	2
---	---	---	---	---	---	---



8/2/99 W. S. **45** **AUG 03 1999**

[illegible]

REV	DATE	BY	APP'D
1	08/21/99	W.J.	W.J.
2	08/21/99	W.J.	W.J.
3	08/21/99	W.J.	W.J.



- NOTES: UNLESS OTHERWISE SPECIFIED
1. ALL DIMENSIONS IN MILLIMETERS.
 2. SURFACE FINISH: PER ANS I Y14.3M-1992
 3. SURFACE TEXTURE: PER ANS I Y14.3M-1992
 4. REMOVE ALL BURRS AND BREAK SHARP EDGES TO A MAXIMUM OF .38
 5. ALL INSIDE CORNERS TO BE .38 RADIUS MAX
 6. ALL DIMENSIONS ARE TO CENTER UNLESS OTHERWISE SPECIFIED
 7. COUNTERSINK: 62-90 DEGREES APPROXIMATELY 76-132 DEEP ALL DRILLED HOLES
 8. PARTS TO BE THOROUGHLY CLEANED TO REMOVE ALL OIL, GREASE, DIRT AND CHIPS
 9. PART NUMBER (DRAWING NO. PLUS DASH NO. PLUS SERIAL NO.) TO BE CLEARLY MARKED ON THE PART ITSELF.


ITEM	QUANTITY	DESCRIPTION	MATERIAL
1	1	STOCK	ALUMINUM 6061-T6
2	2	1.25 IN STD DOWEL, LENGTH 1/2 IN, MAXIMIZER CARRI 83311A171	ALLOY STEEL

8/2/99 W. S.
W. J. AUG 03 1999

ITEM	QUANTITY	DESCRIPTION	MATERIAL
1	1	STOCK	ALUMINUM 6061-T6
2	2	1.25 IN STD DOWEL, LENGTH 1/2 IN, MAXIMIZER CARRI 83311A171	ALLOY STEEL

ITEM	QUANTITY	DESCRIPTION	MATERIAL
1	1	STOCK	ALUMINUM 6061-T6
2	2	1.25 IN STD DOWEL, LENGTH 1/2 IN, MAXIMIZER CARRI 83311A171	ALLOY STEEL

REV	DATE	BY	CHKD	APP'D
1	08/15/99	W.S.	W.S.	W.S.
2	08/15/99	W.S.	W.S.	W.S.
3	08/15/99	W.S.	W.S.	W.S.
4	08/15/99	W.S.	W.S.	W.S.




- NOTES: UNLESS OTHERWISE SPECIFIED
1. ALL DIMENSIONS IN MILLIMETERS
 2. DIMENSIONS TO CENTER UNLESS OTHERWISE SPECIFIED
 3. SURFACE TEXTURE PER ANSIS B 46.1-1995
 4. REMOVE ALL BURRS AND BREAK SHARP EDGES TO A MAXIMUM OF .38
 5. ALL INSIDE CORNERS TO BE .38 RADIUS UNLESS OTHERWISE SPECIFIED
 6. COUNTERSINK 82-90 DEGREES APPROXIMATELY .76-1.52 DEEP ALL DRILLED HOLES
 7. PARTS TO BE THOROUGHLY CLEANED TO REMOVE ALL OIL, GREASE, DIRT AND CHIPS
 8. PART NUMBER (DRAWING NO. PLUS DASH NO. PLUS SERIAL NO.) TO BE CLEARLY MARKED ON THE PART ITSELF.

8/2/99 W. S. W.S. AUG 0 3 1999

ITEM	QUANTITY	DESCRIPTION	MATERIAL
1	1	STOCK	ALUMINUM 6061-T6
2	2	.125 IN STD DOWEL LENGTH 1/2 IN MASTER CARBIDE BRUSHMATT	ALLOY STEEL

UNLESS OTHERWISE SPECIFIED		C/AO GENERATED DRAWING	
DO NOT MANUALLY UPDATE		DO NOT SCALE DRAWING	
DATE	11/11/99	BY	W.S.
DESIGNED	E. HENNING	DATE	11/11/99
CHECKED	H. HADJIOANNIS	DATE	11/11/99
APPROVED	W.S.	DATE	11/11/99


HYTEC, INC		STATION 2 SOUTH	
LENS HOLDER MOUNTING BLOCK		R-C-L-M	
R-C-R-M		2 OF 2	

[illegible][illegible]

- [illegible]

[illegible][illegible][illegible][illegible]

REV	DATE	BY	APP
1	10/11/88	WJH	WJH



METRIC U.S. JAN 18 2000		BROOKHAVEN/PHENIX DWG NO. 002-0212-236	
TITLE: LENS HOLDER MOUNTING BLOCK DESIGNED BY: R-C-T-R-2 DRAWN BY: 142V CHECKED BY: 88516 DATE: 2/1		MATERIAL: ALUMINUM, 6061-T6 PART NO.: 002-0212-236	



PHENIX MuTr STATION 3 SOUTH
INSTALLATION PROCEDURE

procedure name

PHENIX Procedure No. PP-2.5.5.4-11

Revision: A

Date: 4-28-00

Hand Processed Changes

<u>HPC No.</u>	<u>Date</u>	<u>Page Nos.</u>	<u>Initials</u>
<u>1</u>	<u>7/17/00</u>	<u>2 & 3</u>	<u>BJK.</u>
<u> </u>	<u> </u>	<u> </u>	<u> </u>
<u> </u>	<u> </u>	<u> </u>	<u> </u>

Approvals

Peter R... 5/17/00
PHENIX S E & I Date

[Signature] 8 MAY 00
Cognizant Scientist/Engineer Date
/Activity Manager

William L... 5/8/00
PHENIX Safety Date

Charles R... 6/20/00
CA-D ES&H /SAFETY Date

REVISION CONTROL SHEET

LETTER	DESCRIPTION	DATE	WRITTEN BY	APPROVED BY	CURRENT OVERSIGHT
A	First Issue	4/28/2000	n/a	P. Kroon, (1 unintelligible), W. Lenz, C. Pearson	n/a
RETIRED	Installation Completed	3/20/2007	n/a	D. Lynch, P. Giannotti, R. Pisani for PHENIX	D. Lynch

Station 3 South Installation Procedure, PP-2.5.5.4-11

1.0 Purpose and Scope

- 1.1 The purpose of this procedure is to provide direction for the rigging of the station 3 south octants. This procedure will provide detailed instructions for the safe installation of the octants onto their mounting location on the back plate of the magnet

Note that the weight for each octant is 300 lbs.

2.0 Responsibilities

- 2.1 All operations shall be performed under the direction of the PHENIX experimental hall "person-in-charge", or their designee.
- 2.2 Due to the delicacy of this structure, and the critical alignment of its assembly in the magnet, this procedure and all relevant BNL safety guidelines must be strictly adhered to. In accordance with BNL policy, any individual may cease operations if they in any way feel unsafe or if they believe unsafe procedures are being followed, such a complaint shall be reviewed by the cognizant engineer, and if necessary, BNL ES&H Services.
- 2.3 A member of the muon tracking mechanical team should be present for all critical lifts, to consult on procedures and answer any questions as they may arise.

3.0 Prerequisites

- 3.1 Training: All personnel involved in this procedure shall have reviewed this procedure, and be fully knowledgeable about the way in which the octant is mounted in the South magnet. A meeting will take place with all participants involved with this installation to review all aspects and answer any questions that any of the personnel may have. *The crane operation.*
- 3.2 All personnel involved with in this procedure shall have a safety awareness certificate.
- 3.3 All personnel involved in this procedure shall wear hardhats and safety shoes.
- 3.4 Magnet buss has been removed.
- 3.5 All magnet coil water hoses have been reinstalled and leak tested.

4.0 Precautions

- 4.1 The area where rigging operations will be performed shall be cordoned-off to all personnel except the "person in charge" and the technicians assigned to perform this procedure.
- 4.2 Some operations will require personnel to work in close proximity to suspended loads. Do not permit anyone to be positioned under the load.
- 4.3 Lift the octants with the commercial lifting fixture only and only with the protective covers in place on the octant.

5.0 Equipment List

- 5.1 Appropriate ANVER vacuum lifting fixture, model number ET-100M8-MR-SP, serial number 974808, rated load capacity 1000 pounds.

- 5.2 "C" fixture, rated load capacity 1000 pounds
- 5.3 Guide ropes.
- 5.4 Shackles rated for a minimum of 1000-pound load.

6.0 Preparation

- 6.1 Presurvey of the kinematic mounts and octants. See drawing 002-0212-524 B1A and B2A for kinematic mount preset adjustments.
- 6.2 Magnet hoses tested and leak tight.
- 6.3 All kinematic mounts attached to magnet back plate as shown in drawing 002-0212-526 D1,D2 and 002-0212-524 B1,B2,B3
- 6.4 A preliminary trial fit with a station 3 south honeycomb panel should be made by the 1008 crew and muon personnel, to understand the ability and technique needed to safely locate the 6 o'clock octant into the bottom of the magnet. This will make use of both the "C" fixture and the ANVER vacuum lifter. Having the ability of using a full-scale panel along with the required rigging will allow the 1008 crew to get a feel for how difficult working with these large chambers may be.

7.0 Procedure

- 7.1 The side with the kinematic mounts face magnet back plate. Installation proceeds from the bottom of the magnet to the top beginning at 6:00 o'clock and proceeding in order 6:00,4:30,7:30,3:00,9:00,1:30,10:30,12:00.
- 7.2 FIRST OCTANT ONLY _ 6:00 position
 - 7.2.1 Attach "C" fixture to the crane hook and attach the ANVER vacuum-lifting fixture to the "C" fixture using a shackle.
- 7.3 Attach the ANVER lifting fixture to the octant in the horizontal position following the manufacturer instructions. Lift the octant only after the vacuum pump has turned off. Tilt the octant to a vertical position.
 - 7.3.1 For the First octant at 6:00 o'clock the octant may need to be in an intermediate position between 9:00 o'clock and 6:00 o'clock, see drawings numbered 002-0212-566 sheet C1-C8.
- 7.4 Rotate the octant to the orientation in the "spider".
 - 7.4.1 For the First octant at 6:00 o'clock rotate the octant to an intermediate position as it is lowered and then rotate the to the 6:00 o'clock position.
- 7.5 Attach guide ropes to the octant.
- 7.6 Lift and lower the octant into place on the kinematic mounts. Use guide ropes to stabilize the octant during installation. Survey the octant and reset kinematic mounts if necessary.
- 7.7 ~~Have the survey crew look at the targets on the octant and compare the data with the pre-survey data from bldg. 905, along with drawings numbered 002-0212-566, sheets C1 - C8. It is possible to make small adjustments to the kinematic mounts. It will be necessary to remove the octant from the wall to get access to these mounts for location adjustment.~~

OK
7/12/00

8.0 Alignment of octants, alignment system

- 8.1 The survey crew will verify the location of all targets placed on the upstream face of each octant as part of their installation, ~~see 7.7~~ *OK 7/17/0*
- 8.2 Install the camera mounts and cameras to the brass flags located around the outer edge of each octant according the drawings numbered 002-0212-564 and 565.




36 PARMENTER ROAD
HUDSON, MA 01749 USA
508-568-0221 • 800-654-3500
FAX 508-568-1570

ELECTRIC TILTER NO. 820 00 090 MODEL NO. ET100M8-MR-SP

Doc. No. 821 00 090
Revision: A
Effective Date: Nov. 12, 1997

MAXIMUM LOAD SIZE: 11.5 FT. x 11 FT.
LIFTER CAPACITY: 1,000 LBS.
POWER REQUIRED: 115V/1PH/60HZ
UNIT WEIGHT APPROXIMATELY: 540 LBS.




Supersedes:
FROM 8002

REVISION 1 - 20


This drawing, related drawings, & technical information supplied with them are the property of ANVER CORPORATION. All equipment design & application data herein is considered confidential. No use or disclosure thereof may be made without written permission from ANVER CORPORATION.

Classification: SPEC. SHEETS



WJ. NOV 08 1999

Los Alamos Los Alamos National Laboratory 4545 Camino de los Alamos Los Alamos, NM 87545-5076		ORIGINAL, ISSUED BY: [] DATE: [] REVISION: [] DATE: [] REVISION: [] DATE: [] REVISION: []	
PROJECT: MUON SOUTH MAGNET BACKPLATE DETECTOR MOUNTS DRAWING NO. 002-0212-526		TITLE: MUON SOUTH MAGNET BACKPLATE DETECTOR MOUNTS DRAWING NO. 002-0212-526	
DESIGNED BY: CLARK, B-89 P-25 CHECKED BY: [] DATE: [] REVISION: [] DATE: [] REVISION: []		APPROVED BY: [] DATE: [] REVISION: [] DATE: [] REVISION: []	
MATERIAL: NONE FINISH: NONE		PART NO: 128V-267773 D 1	



NOTE:
1. NOT ALL BACKPLATE HOLES ARE REPRESENTED IN THIS VIEW.

MUON SOUTH MAGNET BACKPLATE
SHOWING REAR COIL AND DETECTOR
MOUNTING HOLES

NOTE: HOLE PATTERN LOCATIONS 1, 2, 3 & 4
REFERENCE THE UPPER RIGHT BOLT HOLE.
LOCATIONS 5, 6, 7 & 8 REFERENCE THE UPPER
LEFT BOLT HOLE
THE RECTANGULAR HOLE PATTERN IS
THE SAME AS THE OTHERS, 89.9 X 165.1



○ DENOTES "2" KINEMATIC MOUNT

ALL DIMENSIONS IN MILLIMETERS

Los Alamos Los Alamos National Laboratory Los Alamos, New Mexico 87545		PREPARED BY: [blank] DATE: [blank] DRAWN BY: [blank] DATE: [blank]	
TITLE: MUON SOUTH MAGNET BACKPLATE SHOWING REAR COIL AND DETECTOR MOUNTS		TELEPHONE: (505) 241-1526 FAX: (505) 241-1526 MAILING ADDRESS: [blank]	
MATERIAL: 4-00 P-25		TOTAL NO. OF SHEETS: [blank]	
SHEET NO.: [blank]		TOTAL NO. OF SHEETS: [blank]	
DATE: [blank]		DATE: [blank]	
BY: [blank]		BY: [blank]	
CHECKED BY: [blank]		CHECKED BY: [blank]	
APPROVED BY: [blank]		APPROVED BY: [blank]	

APR 12 2000



NOTE
1. ORIENTATION OF 3/8 THR. ROD
MAY VARY.



CLASSIFICATION				TITLE BLOCK				ORIGINAL ISSUE			
DRAWING	PART	TITLE	DATE	GROUP	REV	CLASS	REVISIONS	DATE	CHANGED BY	CHECKED BY	APPROVED BY
ORIG	SIGNATURE										
BRAIN	CLARK	B/99	P-25								
CHECKED											
PROJ ENGR											
APPROVED											
RELEASED											

LOS ALAMOS				TITLE			
LOS ALAMOS NATIONAL LABORATORY				PHENIX MUON			
LOS ALAMOS, NEW MEXICO, 87545				KINEMATIC MOUNT			
				SUPPORT CONE ASSY			
TOLERANCE - (UNLESS OTHERWISE NOTED)				PHENIX DRAWING NO. 002-0212-524			
X±.0005		ANG±.5		SCALE		TOTAL SHEETS	
X±.0005		.75IN		-		DRAWING NO. 1267-267771	
						SIZE NO. B 1	

ITEM NUMBER RECD DESCRIPTION



ANGULAR POS'N OF THESE BOLTS
WILL VARY BY PANEL LOCATION

NOMINAL SETTING FOR KINEMATIC MOUNT


SUPPORT CONE ASSY


CLASSIFICATION:		PART:		TITLE BLOCK:	
DRAWING:		SIGNATURE:		DATE:	
ORIG:		CLARK		4/00	
DRAWN:		P-25		GROUP:	
CHECKED:					
PROJ ENGR:					
APPROVED:					
RELEASED:					
LOS ALAMOS		ORIGINAL ISSUE		REVISIONS	
LOS ALAMOS NATIONAL LABORATORY		REV		CLASS	
LOS ALAMOS, NEW MEXICO, 87545		REVIS		REVIS	
TOLERANCE - (UNLESS OTHERWISE NOTED)		TITLE		DATE	
X=± 0.001 ± 0.0005		PHEINIX MUON		DRAWN BY	
Y=± 0.001 ± 0.0005		KINEMATIC MOUNT		CHECKED BY	
Z=± 0.001 ± 0.0005		SUPPORT CONE ASSY		APPROVED BY	
SCALE		PHEINIX DRAWING NO. 002-0212-524		SIZE	
.5		TOTAL SHEETS		NO.	
		1267-267771		1A	

5 APR 17 2000

NOTE

1. ORIENTATION OF 3/8 THR. ROD
MAY VARY.


[illegible]



NOMINAL SETTING FOR KINEMATIC MOUNT
SUPPORT SLIDE ASSY

CLASSIFICATION		PART		TITLE BLOCK		ORIGINAL ISSUE		DATE		CHANGED BY	CHECKED BY	APPROVED BY
DRAWING		SIGNATURE		DATE		REV		CLASS		REVISIONS		
DRAWN		CLARK		4/00		P-25		LOS ALAMOS		LOS ALAMOS NATIONAL LABORATORY LOS ALAMOS, NEW MEXICO, 87545		
CHECKED								TOLERANCE - UNLESS OTHERWISE NOTED				
PROJ. ENGR.								X-6 0.10X 56 ANG 5				
APPROVED								X-6 0.100X 5 7 1/2				
RELEASED								.5				
								PHENIX MUON KINEMATIC MOUNT SUPPORT SLIDE ASSY				
								PHENIX DRAWING NO. 002-0212-524				
								SCALE TOTAL SHEETS				
								DRAWING NO. 126Y-267771		SIZE NO. B 2A		

ITEM NUMBER DESCRIPTION



3/8-16UNC
JAM NUT, 3 REOD

SUPPORT STOP ASSY

8 REOD


Z ADJUSTMENT
Y FREEDOM
X FREEDOM

M.S. AUG 20 1993

CLASSIFICATION		PART		TITLE BLOCK		ORIGINAL ISSUE		REVISIONS		DATE		CHANGED BY		CHECKED BY		APPROVED BY	
ORIG		SIGNATURE		DATE	GROUP												
DRAWN		CLARK		B-99	P-25												
CHECKED																	
PROJ ENGR																	
APPROVED																	
RELEASED																	

LOS ALAMOS		TITLE		SCALE		TOTAL SHEETS		DRAWING NO.		SIZE		NO.	
LOS ALAMOS NATIONAL LABORATORY LOS ALAMOS, NEW MEXICO, 87545		PHENIX MUON KINEMATIC MOUNT SUPPORT STOP ASSY		—		126Y-267771 B		002-0212-524		B		3	


TOLERANCE - (UNLESS OTHERWISE NOTED)
X±.0005 ±.0005 ANG±.5
X±.0005 ±.0005 FIN±.5




VIEW SHOWS ORIGINATE DIMENSIONS
FOR (7) LOCATING PINS

5 APR 12 2000


CLASSIFICATION		PART		TITLE BLOCK		REVISION		DATE		BY		CHECKED		DATE		BY	
ORIGIN		CLARK		4/00 P-25		LOS ALAMOS		MOON STATION 3 SOUTH		LOCATING PINS		105		1287-287787		C 1	
DESIGNED		CLARK		4/00 P-25		LOS ALAMOS NATIONAL LABORATORY		LOS ALAMOS, NEW MEXICO, 87545		SCALE		1:1		1287-287787		C 1	
CHECKED		CLARK		4/00 P-25		LOS ALAMOS NATIONAL LABORATORY		LOS ALAMOS, NEW MEXICO, 87545		SCALE		1:1		1287-287787		C 1	
APPROVED		CLARK		4/00 P-25		LOS ALAMOS NATIONAL LABORATORY		LOS ALAMOS, NEW MEXICO, 87545		SCALE		1:1		1287-287787		C 1	
REVISION		CLARK		4/00 P-25		LOS ALAMOS NATIONAL LABORATORY		LOS ALAMOS, NEW MEXICO, 87545		SCALE		1:1		1287-287787		C 1	

[illegible]




W.S. APR 12 2000

[illegible]



W.S. APR 12 2000

[illegible]



VIEW SHOWS ORIGINATE DIMENSIONS FOR 171 LOCATING PINS

U.S. APR 12 2000

CLASSIFICATION		PROJECT		TITLE & ROOM	
DATE	BY	DATE	BY	DATE	BY
01/12/00	CLARK	4/7/00	P-25		
LOS ALAMOS LOS ALAMOS NATIONAL LABORATORY LOS ALAMOS, NEW MEXICO, 87545					
TITLE LOS ALAMOS STATION 3 SOUTH LOCATING PINS, BOT SIDE L					
PROJECT NO. 002-0212-568 DRAWING NO. 1287-207796 SHEET NO. 1 OF 1					

[illegible]



PHENIX MuTr SOUTH SPIDER INSTALLATION PROCEDURE

procedure name

PHENIX Procedure No. PP-2.5.5.4-12

Revision: A

Date: 4-28-00

Hand Processed Changes

<u>HPC No.</u>	<u>Date</u>	<u>Page Nos.</u>	<u>Initials</u>
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

Approvals

PJ Koon 5/10/00
PHENIX S E & I Date

[Signature] 8 May 00
Cognizant Scientist/Engineer Date
/Activity Manager

[Signature] 5/2/00
PHENIX Safety Date

CA-D ES&H /SAFETY Date

In House Procedure

PHENIX Procedure # PP-2.5.5.4-12 Rev A

REVISION CONTROL SHEET

LETTER	DESCRIPTION	DATE	WRITTEN BY	APPROVED BY	CURRENT OVERSIGHT
A	First Issue	4/28/2000	n/a	P. Kroon, (1 unintelligible), W. Lenz	n/a
RETIRED	Installation Completed	3/20/2007	n/a	D. Lynch, P. Giannotti, R. Pisani for PHENIX	D. Lynch

Station 2 South Spider Installation Procedure PP-2.5.5.4-12

1.0 Purpose and Scope

- 1.1 The purpose of this procedure is to provide direction for the rigging of the station 2 south support "spider". This structure locates all eight station 2 detectors in the South muon magnet. This procedure will provide detailed instructions for the safe installation of the support "spider" onto its mounting location off the back of the "teacup" and flanges on the bottom three lampshade panels.

Note that the weight for each half of the "spider" is 350 pounds. Each spanner weldment bar is an additional 30 pounds.

2.0 Responsibilities

- 2.1 All operations shall be performed under the direction of the PHENIX experimental hall "person-in-charge", or their designee.
- 2.2 Due to the delicacy of this structure, and the critical alignment of its assembly in the magnet, this procedure and all relevant BNL safety guidelines must be strictly adhered to. In accordance with BNL policy, any individual may cease operations if they in any way feel unsafe or if they believe unsafe procedures are being followed, such a complaint shall be reviewed by the cognizant engineer, and if necessary, BNL ES&H Services.
- 2.3 A member of the muon tracking mechanical team should be present for all critical lifts, to consult on procedures and answer any questions as they may arise.

3.0 Prerequisites

- 3.1 Training: All personnel involved in this procedure shall have reviewed this procedure, and be fully knowledgeable about the way in which the support "spider" is assembled in the South magnet. A meeting will take place with all participants involved with this installation to review all aspects and answer any questions that any of the personnel may have.
- 3.2 All personnel involved with in this procedure shall have a safety awareness certificate.
- 3.3 All personnel involved in this procedure shall wear hardhats and safety shoes.
- 3.4 Magnet power buss must be removed.

4.0 Precautions

- 4.1 The area where rigging operations will be performed shall be cordoned-off to all personnel except the "person in charge" and the technicians assigned to perform this procedure.
- 4.2 Some operations will require personnel to work in close proximity to suspended loads. Do not permit anyone to be positioned under the load.
- 4.3 Lift half spiders only by the swivel eyes attached to the hub. (See drawings numbered 002-0212-260, sheets D2, D3, D4 and D5.

5.0 Equipment List

- 5.1 Appropriate slings for lifting 1000 pounds and shackles

- 5.2 Two-3/8-16 lifting swivel eyes (supplied by Ray Savino) – Jergens part # 23408 rated for 1000 pounds each.
- 5.3 Guide ropes. May be attached to outer bars to help stabilize.
- 5.4 Torque wrench.

6.0 Preparation

- 6.1 Mount 12 FR4 support brackets to top half of spider using 3/8-16 x 1-3/4 inch stainless steel socket head cap screws (provided by Ray Savino). Drawing number 002-0212-262 D1. On the lower half spider attach FR4 brackets as called out on drawing 002-0212-260 D1. On the two splice tube weldments attach 6 FR4 brackets as indicated on drawing 002-0212-260-D1. Torque for a 3/8-16 stainless steel bolt is 236 in-lbs.
- 6.2 For each half spider install 9-3/8-16 x 2 inch long set screws where indicated on the hub on drawing 002-0212-260 D4-5.
- 6.3 Place the bottom half of the spider in the bottom of the magnet. Attach two slings to two swivel eyes screwed into the center hub. Attach a rope to the outer cross bar that match the 6 o'clock octant to stabilize and to pull across from the underside of the piston. Lower the bottom half of the spider along the side of the bottom lampshade panel and pull the rope so that this piece will lay flat in the bottom of the magnet. It will need to be rotated so that it can be lifted up from the bottom of the magnet, after the top half is installed. See 7.2.

7.0 Procedure

7.1 Top half spider

- 7.1.1 The spokes are on the upstream side of the assembly. The hub extends in the downstream direction towards the magnet back plate.
- 7.1.2 Attach two slings, in a choker around the interface of the three legs that would be on either side of the 12 o'clock octant.
- 7.1.3 Attach guide ropes to stabilize the piece from rotating. Note: for 7.1.2 and 7.1.3 see drawings numbered 002-0212-260, sheet D2.
- 7.1.4 Lift and lower the top half spider into place and attach to the teacup at the outside boundary using two 1/2-13 stainless steel bolts per FR-4 block, these screws will be tightened later in the assembly process. Put set screws into the hub at 6 locations to support the hub off of the piston.

7.2 Bottom half spider.


- 7.2.1 The spokes are in the upstream side of the assembly. The hub extends in the downstream direction.
- 7.2.2 Attach four swivel eyes to the hub in the upstream, (spoke side) location where the two halves join together and attach a sling to each of the pair of swivel eyes and run up on either side of the piston.
- 7.2.3 On either side a 1/8 inch aluminum spacer is placed between the two half hubs. Install 3/8-16 socket head screws and tighten to 236 in-lbs. Attach outer spider to the tea cup flange using two 1/2-13 stainless steel bolts per FR-4 block, do not tighten.

- 7.2.4 Install splice tubes as shown on drawing 002-0212-260 sheet D1. Use long 3/8-16 bolts to make connection with top and bottom halves of the spider. Torque 3/8-16 stainless steel bolts to 236 in-lbs.

8.0 Alignment

- 8.1 Survey crew can make some small adjustments to the location of the spider, once the two halves are bolted together, using the long setscrews that go through the hub to the piston notch. After the spider is located correctly, tighten all 1/2-13 bolts around the perimeter to the teacup and lampshade panels to a torque of 517 in-lbs. remove the setscrews from the hub to the piston. Measure continuity to the piston to make sure that the piston is not in electrical contact with the spider.

REV	DESCRIPTION	DATE	BY
1	24/05/2018		




- NOTES: UNLESS OTHERWISE SPECIFIED
1. ALL DIMENSIONS IN MILLIMETERS.
 2. DIMENSIONS AND TOLERANCING PER ANASIS Y14.5M-1994
 3. SURFACE TEXTURE PER AMS/ASME B.46.1-1995
 4. REMOVE ALL BURRS TO BEAT SHARP EDGES TO A MAXIMUM OF .015
 5. ALL DIMENSIONS TO BE SHOWN UNLESS OTHERWISE SPECIFIED
 6. COUNTERSINK 82 DEGREES APPROXIMATELY .03/.08 DEEP ALL DRILLED HOLES
 7. COUNTERSINK 82 DEGREES APPROXIMATELY .03/.08 DEEP ALL DRILLED HOLES
 8. PART NUMBER DRAWING NO., DASH NO., REVISION NO., SERIAL NO.) TO BE CLEARLY MARKED ON THE PART ITSELF.

NO. 5, OCT 13 1999

ITEM NO.	QTY.	PART NO.	DESCRIPTION	MATERIAL
1	1	002-0212-262-02	Support Block	303
2	1		1/4 x 1/4 x 1/4 UNC-2A x 1.75 Lg.	303
3	1		Flat Washer, 1/2	303
4	1		1/4 x 1/4 x 1/4 UNC-2A x 1.75 Lg.	303

HYTEC, INC PHENIX STATION 2 SOUTH SPIDER SUPPORT BRACKET ASSY		002-0212-262 D 1
---	--	------------------------

8	7	6	5	4	3	2	1
---	---	---	---	---	---	---	---



OTHER: UNLESS OTHERWISE SPECIFIED

ALL DIMENSIONS IN MILLIMETERS

STANDARD TOLERANCES: FRACTIONAL DIMENSIONS: ±0.25 (1/16) UNLESS OTHERWISE SPECIFIED

REMOVE ALL BURRS AND BREAK SHARP EDGES TO A MAXIMUM OF .015


ALL INTERIOR RADIUSES ARE .015 UNLESS OTHERWISE SPECIFIED

COUNTERSINK OR DEGRESS APPROXIMATELY 100° DEEP, ALL DRILLED HOLES



PARTS TO BE DRAWING NO. (DASH NO.) REVISION NO. (SERIAL NO.) TO BE CLEARLY MARKED

ON THE PART ITSELF.

REV	DATE	DESCRIPTION	BY	CHKD	THROWING
1	01/11/1994	1.000	11/11/94	11/11/94	11/11/94
2	01/11/1994	2.000	11/11/94	11/11/94	11/11/94
3	01/11/1994	3.000	11/11/94	11/11/94	11/11/94
4	01/11/1994	4.000	11/11/94	11/11/94	11/11/94
5	01/11/1994	5.000	11/11/94	11/11/94	11/11/94
6	01/11/1994	6.000	11/11/94	11/11/94	11/11/94
7	01/11/1994	7.000	11/11/94	11/11/94	11/11/94
8	01/11/1994	8.000	11/11/94	11/11/94	11/11/94
9	01/11/1994	9.000	11/11/94	11/11/94	11/11/94
10	01/11/1994	10.000	11/11/94	11/11/94	11/11/94
11	01/11/1994	11.000	11/11/94	11/11/94	11/11/94
12	01/11/1994	12.000	11/11/94	11/11/94	11/11/94
13	01/11/1994	13.000	11/11/94	11/11/94	11/11/94
14	01/11/1994	14.000	11/11/94	11/11/94	11/11/94
15	01/11/1994	15.000	11/11/94	11/11/94	11/11/94
16	01/11/1994	16.000	11/11/94	11/11/94	11/11/94
17	01/11/1994	17.000	11/11/94	11/11/94	11/11/94
18	01/11/1994	18.000	11/11/94	11/11/94	11/11/94
19	01/11/1994	19.000	11/11/94	11/11/94	11/11/94
20	01/11/1994	20.000	11/11/94	11/11/94	11/11/94
21	01/11/1994	21.000	11/11/94	11/11/94	11/11/94
22	01/11/1994	22.000	11/11/94	11/11/94	11/11/94
23	01/11/1994	23.000	11/11/94	11/11/94	11/11/94
24	01/11/1994	24.000	11/11/94	11/11/94	11/11/94
25	01/11/1994	25.000	11/11/94	11/11/94	11/11/94
26	01/11/1994	26.000	11/11/94	11/11/94	11/11/94
27	01/11/1994	27.000	11/11/94	11/11/94	11/11/94
28	01/11/1994	28.000	11/11/94	11/11/94	11/11/94
29	01/11/1994	29.000	11/11/94	11/11/94	11/11/94
30	01/11/1994	30.000	11/11/94	11/11/94	11/11/94
31	01/11/1994	31.000	11/11/94	11/11/94	11/11/94
32	01/11/1994	32.000	11/11/94	11/11/94	11/11/94
33	01/11/1994	33.000	11/11/94	11/11/94	11/11/94
34	01/11/1994	34.000	11/11/94	11/11/94	11/11/94
35	01/11/1994	35.000	11/11/94	11/11/94	11/11/94
36	01/11/1994	36.000	11/11/94	11/11/94	11/11/94
37	01/11/1994	37.000	11/11/94	11/11/94	11/11/94
38	01/11/1994	38.000	11/11/94	11/11/94	11/11/94
39	01/11/1994	39.000	11/11/94	11/11/94	11/11/94
40	01/11/1994	40.000	11/11/94	11/11/94	11/11/94
41	01/11/1994	41.000	11/11/94	11/11/94	11/11/94
42	01/11/1994	42.000	11/11/94	11/11/94	11/11/94
43	01/11/1994	43.000	11/11/94	11/11/94	11/11/94
44	01/11/1994	44.000	11/11/94	11/11/94	11/11/94
45	01/11/1994	45.000	11/11/94	11/11/94	11/11/94
46	01/11/1994	46.000	11/11/94	11/11/94	11/11/94
47	01/11/1994	47.000	11/11/94	11/11/94	11/11/94
48	01/11/1994	48.000	11/11/94	11/11/94	11/11/94
49	01/11/1994	49.000	11/11/94	11/11/94	11/11/94
50	01/11/1994	50.000	11/11/94	11/11/94	11/11/94
51	01/11/1994	51.000	11/11/94	11/11/94	11/11/94
52	01/11/1994	52.000	11/11/94	11/11/94	11/11/94
53	01/11/1994	53.000	11/11/94	11/11/94	11/11/94
54	01/11/1994	54.000	11/11/94	11/11/94	11/11/94
55	01/11/1994	55.000	11/11/94	11/11/94	11/11/94
56	01/11/1994	56.000	11/11/94	11/11/94	11/11/94
57	01/11/1994	57.000	11/11/94	11/11/94	11/11/94
58	01/11/1994	58.000	11/11/94	11/11/94	11/11/94
59	01/11/1994	59.000	11/11/94	11/11/94	11/11/94
60	01/11/1994	60.000	11/11/94	11/11/94	11/11/94
61	01/11/1994	61.000	11/11/94	11/11/94	11/11/94
62	01/11/1994	62.000	11/11/94	11/11/94	11/11/94
63	01/11/1994	63.000	11/11/94	11/11/94	11/11/94
64	01/11/1994	64.000	11/11/94	11/11/94	11/11/94
65	01/11/1994	65.000	11/11/94	11/11/94	11/11/94
66	01/11/1994	66.000	11/11/94	11/11/94	11/11/94
67	01/11/1994	67.000	11/11/94	11/11/94	11/11/94
68	01/11/1994	68.000	11/11/94	11/11/94	11/11/94
69	01/11/1994	69.000	11/11/94	11/11/94	11/11/94
70	01/11/1994	70.000	11/11/94	11/11/94	11/11/94
71	01/11/1994	71.000	11/11/94	11/11/94	11/11/94
72	01/11/1994	72.000	11/11/94	11/11/94	11/11/94
73	01/11/1994	73.000	11/11/94	11/11/94	11/11/94
74	01/11/1994	74.000	11/11/94	11/11/94	11/11/94
75	01/11/1994	75.000	11/11/94	11/11/94	11/11/94
76	01/11/1994	76.000	11/11/94	11/11/94	11/11/94
77	01/11/1994	77.000	11/11/94	11/11/94	11/11/94
78	01/11/1994	78.000	11/11/94	11/11/94	11/11/94
79	01/11/1994	79.000	11/11/94	11/11/94	11/11/94
80	01/11/1994	80.000	11/11/94	11/11/94	11/11/94
81	01/11/1994	81.000	11/11/94	11/11/94	11/11/94
82	01/11/1994	82.000	11/11/94	11/11/94	11/11/94
83	01/11/1994	83.000	11/11/94	11/11/94	11/11/94
84	01/11/1994	84.000	11/11/94	11/11/94	11/11/94
85	01/11/1994	85.000	11/11/94	11/11/94	11/11/94
86	01/11/1994	86.000	11/11/94	11/11/94	11/11/94
87	01/11/1994	87.000	11/11/94	11/11/94	11/11/94
88	01/11/1994	88.000	11/11/94	11/11/94	11/11/94
89	01/11/1994	89.000	11/11/94	11/11/94	11/11/94
90	01/11/1994	90.000	11/11/94	11/11/94	11/11/94
91	01/11/1994	91.000	11/11/94	11/11/94	11/11/94
92	01/11/1994	92.000	11/11/94	11/11/94	11/11/94
93	01/11/1994	93.000	11/11/94	11/11/94	11/11/94
94	01/11/1994	94.000	11/11/94	11/11/94	11/11/94
95	01/11/1994	95.000	11/11/94	11/11/94	11/11/94
96	01/11/1994	96.000	11/11/94	11/11/94	11/11/94
97	01/11/1994	97.000	11/11/94	11/11/94	11/11/94
98	01/11/1994	98.000	11/11/94	11/11/94	11/11/94
99	01/11/1994	99.000	11/11/94	11/11/94	11/11/94
100	01/11/1994	100.000	11/11/94	11/11/94	11/11/94



DETAIL A
SCALE 1:1






MATERIAL: 304 STAINLESS STEEL

WSS APR 20 2000

- NOTES: UNLESS OTHERWISE SPECIFIED
1. ALL DIMENSIONS IN MILLIMETERS
 2. SURFACE TEXTURE PER ANSI B 46.1-1988
 3. SURFACE FINISH: 320 R.A. MAX
 4. ALL INSIDE CORNERS TO BE .015 RADIUS MAX
 5. COUPLERSINK 82 DEGREES ALL TAPPED HOLES TO MAJOR DIAMETER
 6. COUPLERSINK 82 DEGREES ALL TAPPED HOLES TO MAJOR DIAMETER
 7. PARTS TO BE CLEANED TO REMOVE ALL OIL, GREASE, DIRT AND CHIPS
 8. PART NUMBER DRAWING NO., DASH NO., REVISION NO., SERIAL NO.) TO BE CLEARLY MARKED ON THE PART ITSELF.

HYTEC, INC		PHENIX STATION 2 SOUTH SPIDER LOWER SUPPORT RING	
PROJECT	002-0212-260-D-5-1	DATE	002-0212-260 D 5
DESIGNED	10/09/93	CHECKED	10/09/93
DRAWN	10/09/93	APPROVED	10/09/93
SCALE	1:1	TITLE	WSS


[illegible]

MATERIAL: 304 STAINLESS STEEL

UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES TOLERANCES ARE:		CAD GENERATED DRAWING DO NOT MANUALLY UPDATE DO NOT SCALE DRAWING	
FINISHES: 1 = AS BUILT 2 = PAINT 3 = GALVANNEAL 4 = POLYESTER 5 = POLYURETHANE 6 = POLYURETHANE 7 = POLYURETHANE 8 = POLYURETHANE 9 = POLYURETHANE 10 = POLYURETHANE 11 = POLYURETHANE 12 = POLYURETHANE 13 = POLYURETHANE 14 = POLYURETHANE 15 = POLYURETHANE 16 = POLYURETHANE 17 = POLYURETHANE 18 = POLYURETHANE 19 = POLYURETHANE 20 = POLYURETHANE 21 = POLYURETHANE 22 = POLYURETHANE 23 = POLYURETHANE 24 = POLYURETHANE 25 = POLYURETHANE 26 = POLYURETHANE 27 = POLYURETHANE 28 = POLYURETHANE 29 = POLYURETHANE 30 = POLYURETHANE 31 = POLYURETHANE 32 = POLYURETHANE 33 = POLYURETHANE 34 = POLYURETHANE 35 = POLYURETHANE 36 = POLYURETHANE 37 = POLYURETHANE 38 = POLYURETHANE 39 = POLYURETHANE 40 = POLYURETHANE 41 = POLYURETHANE 42 = POLYURETHANE 43 = POLYURETHANE 44 = POLYURETHANE 45 = POLYURETHANE 46 = POLYURETHANE 47 = POLYURETHANE 48 = POLYURETHANE 49 = POLYURETHANE 50 = POLYURETHANE 51 = POLYURETHANE 52 = POLYURETHANE 53 = POLYURETHANE 54 = POLYURETHANE 55 = POLYURETHANE 56 = POLYURETHANE 57 = POLYURETHANE 58 = POLYURETHANE 59 = POLYURETHANE 60 = POLYURETHANE 61 = POLYURETHANE 62 = POLYURETHANE 63 = POLYURETHANE 64 = POLYURETHANE 65 = POLYURETHANE 66 = POLYURETHANE 67 = POLYURETHANE 68 = POLYURETHANE 69 = POLYURETHANE 70 = POLYURETHANE 71 = POLYURETHANE 72 = POLYURETHANE 73 = POLYURETHANE 74 = POLYURETHANE 75 = POLYURETHANE 76 = POLYURETHANE 77 = POLYURETHANE 78 = POLYURETHANE 79 = POLYURETHANE 80 = POLYURETHANE 81 = POLYURETHANE 82 = POLYURETHANE 83 = POLYURETHANE 84 = POLYURETHANE 85 = POLYURETHANE 86 = POLYURETHANE 87 = POLYURETHANE 88 = POLYURETHANE 89 = POLYURETHANE 90 = POLYURETHANE 91 = POLYURETHANE 92 = POLYURETHANE 93 = POLYURETHANE 94 = POLYURETHANE 95 = POLYURETHANE 96 = POLYURETHANE 97 = POLYURETHANE 98 = POLYURETHANE 99 = POLYURETHANE 100 = POLYURETHANE		MATERIALS: 1 = AS BUILT 2 = PAINT 3 = GALVANNEAL 4 = POLYESTER 5 = POLYURETHANE 6 = POLYURETHANE 7 = POLYURETHANE 8 = POLYURETHANE 9 = POLYURETHANE 10 = POLYURETHANE 11 = POLYURETHANE 12 = POLYURETHANE 13 = POLYURETHANE 14 = POLYURETHANE 15 = POLYURETHANE 16 = POLYURETHANE 17 = POLYURETHANE 18 = POLYURETHANE 19 = POLYURETHANE 20 = POLYURETHANE 21 = POLYURETHANE 22 = POLYURETHANE 23 = POLYURETHANE 24 = POLYURETHANE 25 = POLYURETHANE 26 = POLYURETHANE 27 = POLYURETHANE 28 = POLYURETHANE 29 = POLYURETHANE 30 = POLYURETHANE 31 = POLYURETHANE 32 = POLYURETHANE 33 = POLYURETHANE 34 = POLYURETHANE 35 = POLYURETHANE 36 = POLYURETHANE 37 = POLYURETHANE 38 = POLYURETHANE 39 = POLYURETHANE 40 = POLYURETHANE 41 = POLYURETHANE 42 = POLYURETHANE 43 = POLYURETHANE 44 = POLYURETHANE 45 = POLYURETHANE 46 = POLYURETHANE 47 = POLYURETHANE 48 = POLYURETHANE 49 = POLYURETHANE 50 = POLYURETHANE 51 = POLYURETHANE 52 = POLYURETHANE 53 = POLYURETHANE 54 = POLYURETHANE 55 = POLYURETHANE 56 = POLYURETHANE 57 = POLYURETHANE 58 = POLYURETHANE 59 = POLYURETHANE 60 = POLYURETHANE 61 = POLYURETHANE 62 = POLYURETHANE 63 = POLYURETHANE 64 = POLYURETHANE 65 = POLYURETHANE 66 = POLYURETHANE 67 = POLYURETHANE 68 = POLYURETHANE 69 = POLYURETHANE 70 = POLYURETHANE 71 = POLYURETHANE 72 = POLYURETHANE 73 = POLYURETHANE 74 = POLYURETHANE 75 = POLYURETHANE 76 = POLYURETHANE 77 = POLYURETHANE 78 = POLYURETHANE 79 = POLYURETHANE 80 = POLYURETHANE 81 = POLYURETHANE 82 = POLYURETHANE 83 = POLYURETHANE 84 = POLYURETHANE 85 = POLYURETHANE 86 = POLYURETHANE 87 = POLYURETHANE 88 = POLYURETHANE 89 = POLYURETHANE 90 = POLYURETHANE 91 = POLYURETHANE 92 = POLYURETHANE 93 = POLYURETHANE 94 = POLYURETHANE 95 = POLYURETHANE 96 = POLYURETHANE 97 = POLYURETHANE 98 = POLYURETHANE 99 = POLYURETHANE 100 = POLYURETHANE	
002-0212-260-D-41		002-0212-260 D 4	

1. NOTE: UNLESS OTHERWISE SPECIFIED
2. DIMENSIONS AND TOLERANCING PER ASME Y14.5M-1994
3. REMOVE ALL BURRS AND BREAK SHARP EDGES TO A MAXIMUM OF .015
4. ALL INSIDE CORNERS TO BE RADIUS UNLESS OTHERWISE SPECIFIED
5. COATING IS TO BE APPROXIMATELY .0025 DEEP FOR MAJOR DIAMETER
6. COATING IS TO BE APPROXIMATELY .0075 DEEP FOR MINOR DIAMETER
7. PART LABEL LOCATING NO., DRAWING NO., REVISION NO., SERIAL NO.) TO BE CLEARLY MARKED ON THE PART ITSELF.

REV	DATE	DESCRIPTION	BY	CHKD
1	04/20/2000	Initial Design	W. J. Smith	J. D. Jones
2	04/20/2000	Revised Design	W. J. Smith	J. D. Jones
3	04/20/2000	Revised Design	W. J. Smith	J. D. Jones
4	04/20/2000	Revised Design	W. J. Smith	J. D. Jones
5	04/20/2000	Revised Design	W. J. Smith	J. D. Jones
6	04/20/2000	Revised Design	W. J. Smith	J. D. Jones
7	04/20/2000	Revised Design	W. J. Smith	J. D. Jones
8	04/20/2000	Revised Design	W. J. Smith	J. D. Jones



- NOTES: UNLESS OTHERWISE SPECIFIED
1. ALL DIMENSIONS IN MILLIMETERS
 2. SURFACE TEXTURE PER ANS B 46.1-1995
 3. ALL DIMENSIONS TO A MAXIMUM OF .015
 4. ALL DIMENSIONS TO A MAXIMUM OF .015
 5. ALL DIMENSIONS TO A MAXIMUM OF .015
 6. ALL DIMENSIONS TO A MAXIMUM OF .015
 7. ALL DIMENSIONS TO A MAXIMUM OF .015
 8. ALL DIMENSIONS TO A MAXIMUM OF .015
 9. ALL DIMENSIONS TO A MAXIMUM OF .015
 10. ALL DIMENSIONS TO A MAXIMUM OF .015

DETAIL B
SCALE 1:2

DETAIL A
SCALE 1:1

APR 20 2000


ITEM NO.	QTY.	PART NO.	DESCRIPTION
1	1	002-0212-260-D3	Lower Support Ring
2	2	002-0212-260-D10	Outer Radial Spoke
3	2	002-0212-260-D9	Central Radial Spoke
4	2	002-0212-260-D8	Rear Chamber Support
5	1	002-0212-260-D7	Front Chamber Support

DATE	BY	CHKD	APP'D
002-0212-260-D3-1	W. J. Smith	J. D. Jones	J. D. Jones


DATE	BY	CHKD	APP'D
002-0212-260-D3-1	W. J. Smith	J. D. Jones	J. D. Jones

DATE	BY	CHKD	APP'D
002-0212-260-D3-1	W. J. Smith	J. D. Jones	J. D. Jones

REV	DATE	DESCRIPTION	BY	CHKD
1	04/20/2000	ISSUED FOR MANUFACTURE	WJ	WJ
2	04/20/2000	REVISION	WJ	WJ
3	04/20/2000	REVISION	WJ	WJ
4	04/20/2000	REVISION	WJ	WJ
5	04/20/2000	REVISION	WJ	WJ
6	04/20/2000	REVISION	WJ	WJ
7	04/20/2000	REVISION	WJ	WJ
8	04/20/2000	REVISION	WJ	WJ







- NOTES: UNLESS OTHERWISE SPECIFIED
1. ALL DIMENSIONS IN MILLIMETERS
 2. DIMENSIONS AND TOLERANCING PER ASME Y14.5M-1994
 3. SURFACE TEXTURE PER ANS B 46.1-1995
 4. REMOVE ALL CHIPS AND BURRS FROM ALL EDGES TO A MAXIMUM OF .015
 5. ALL DIMENSIONS UNLESS OTHERWISE SPECIFIED ARE TO THE CENTERLINE
 6. COUNTERSINK 62 DEGREES APPROXIMATELY .001 DEEP ALL DRILLED HOLES
 7. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 8. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 9. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 10. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 11. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 12. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 13. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 14. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 15. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 16. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 17. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 18. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 19. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 20. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 21. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 22. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 23. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 24. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 25. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 26. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 27. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 28. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 29. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 30. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 31. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 32. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 33. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 34. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 35. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 36. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 37. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 38. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 39. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 40. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 41. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 42. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 43. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 44. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 45. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 46. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 47. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 48. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 49. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 50. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 51. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 52. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 53. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 54. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 55. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 56. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 57. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 58. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 59. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 60. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 61. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 62. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 63. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 64. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 65. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 66. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 67. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 68. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 69. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 70. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 71. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 72. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 73. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 74. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 75. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 76. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 77. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 78. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 79. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 80. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 81. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 82. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 83. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 84. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 85. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 86. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 87. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 88. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 89. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 90. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 91. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 92. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 93. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 94. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 95. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 96. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 97. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 98. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 99. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS
 100. PARTS TO BE HONED/CLEANED TO REMOVE ALL DRILL CHIPS



ITEM NO.	QTY.	PART NO.	DESCRIPTION
1	1	002-0212-260-D4	Upper Support Ring
2	2	002-0212-260-D10	Outer Radial Spoke
3	2	002-0212-260-D5	Central Radial Spoke
4	2	002-0212-260-D6	Rear Chamber Support
5	1	002-0212-260-D7	Front Chamber Support

HYTEC, INC.
PHENIX STATION 2 SOUTH
SPIDER.
TOP FRAME SUBASSEMBLY
002-0212-260 D 2



DETAIL A
SCALE 1:6


- NOTES: UNLESS OTHERWISE SPECIFIED
1. ALL DIMENSIONS IN MILLIMETERS.
 2. DIMENSIONS AND TOLERANCES PER ANSI Y14.5M-1994.
 3. SURFACE TEXTURE PER AMS/ASME B 46.1-1995.
 4. REMOVE ALL BURRS AND BREAK SHARP EDGES TO A MAXIMUM OF .015.
 5. FINISH ALL SURFACES TO A MAXIMUM OF .015.
 6. COUNTERSINK 22 DEGREES APPROXIMATELY .03/.06 DEEP ALL DRILLED HOLES.
 7. PARTS TO BE THOROUGHLY CLEANED TO REMOVE ALL OIL/GREASE, DIRT AND CURS.
 8. ON THE PART ITSELF.
 9. DRAWING NO. DASH NO. REVISION NO. (SERIAL NO.) TO BE CLEARLY MARKED.

02-02-260

ITEM NO.	QTY.	PART NO.	DESCRIPTION	MATERIAL
1	1	002-0212-260-02	TOP FRAME SUB-ASSEMBLY	
2	1	002-0212-260-03	BOTTOM FRAME SUB-ASSEMBLY	
3	2	002-0212-260-06	SPLICE TUBE WEIGHT	SSST
4	8		SOC HD SCREW, 3/8-16 UNC-2A X 1.25 LG.	SSST
5	14		SOC HD SCREW, 3/8-16 UNC-2A X 3.75 LG.	SSST
6	16		FLAT WASHER, 3/8"	SSST
7	8	002-0212-260-01	Hex NUT, 3/16 UNC-2B	
8	8		Inner Detector Stabilizer	
9	18	002-0212-260-01	Support Bracket Assembly	
10	3	002-0212-260-01	Right Support Bracket Assembly	
11	3	002-0212-260-01	Left Support Bracket Assembly	

UNLESS OTHERWISE SPECIFIED DIMENSIONS TOLERANCES SURFACE FINISH: 12		CAN BE GENERATED DRAWING DO NOT MANUALLY UPDATE SCALE DRAWING		HYTEC, INC	
PART NO. 002-0212260-D1-1		REV 002-0212-260 D 1		PHENIX STATION 2 SOUTH SPIDER SUPPORT ASSEMBLY	

REV	DESCRIPTION	DATE	APPROVED




- NOTES: UNLESS OTHERWISE SPECIFIED
1. ALL DIMENSIONS IN MILLIMETERS
 2. DIMENSIONS AND TOLERANCING PER ANASIZ Y14.5M-1994
 3. REMOVE ALL BURRS AND BREAK ALL SHARP EDGES TO A MAXIMUM OF .015
 4. ALL INSIDE CORNERS TO BE .015 RADIUS MAX
 5. COUNTERSINK 82 DEGREES ALL TAPPED HOLES TO MAJOR DIAMETER
 6. PARTS TO BE THOROUGHLY CLEANED TO REMOVAL OF ALL OIL, GREASE, AND CHIPS
 7. PART NUMBER (DRAWING NO., DASH NO., REVISION NO., SERIAL NO.) TO BE CLEARLY MARKED ON THE PART ITSELF.

W.S. OCT 13 1999

ITEM NO.	QTY.	PART NO.	DESCRIPTION	MATERIAL
1	1	002-0212-264-D1	RIGHT SUPPORT BRACKET	SS1
2	1		PHENIX STATION 2 SOUTH SPIDER SUPPORT RIGHT BRACKET ASSY	SS1
3	1		PHENIX STATION 2 SOUTH SPIDER SUPPORT RIGHT BRACKET ASSY	SS1
4	1		PHENIX STATION 2 SOUTH SPIDER SUPPORT RIGHT BRACKET ASSY	SS1

UNLESS OTHERWISE SPECIFIED DIMENSIONS AND TOLERANCING PER ANASIZ Y14.5M-1994 REMOVE ALL BURRS AND BREAK ALL SHARP EDGES TO A MAXIMUM OF .015 ALL INSIDE CORNERS TO BE .015 RADIUS MAX COUNTERSINK 82 DEGREES ALL TAPPED HOLES TO MAJOR DIAMETER PARTS TO BE THOROUGHLY CLEANED TO REMOVAL OF ALL OIL, GREASE, AND CHIPS PART NUMBER (DRAWING NO., DASH NO., REVISION NO., SERIAL NO.) TO BE CLEARLY MARKED ON THE PART ITSELF.		CAD GENERATED DRAWING DO NOT MANUALLY UPDATE DO NOT SCALE DRAWING	
DRAWN: [Signature] CHECKED: [Signature] APPROVED: [Signature]		DATE: 10-13-99 TIME: 10:00 AM BY: [Signature]	
PART NO. 002-0212-264-D1-1		HYTEC, INC. PHENIX STATION 2 SOUTH SPIDER SUPPORT RIGHT BRACKET ASSY	

REV	DESCRIPTION	DATE	APPROVED



- NOTES: UNLESS OTHERWISE SPECIFIED
1. ALL DIMENSIONS IN MILLIMETERS
 2. DIMENSIONS AND TOLERANCING PER ANSI Y14.5M-1994
 3. SURFACE TEXTURE PER ANISME B 46.1-1995
 4. REMOVE ALL BURRS AND BREAK SHARP EDGES TO A MAXIMUM OF .015
 5. ALL DIMENSIONS TO BE TAKEN FROM THE CENTERLINE UNLESS OTHERWISE SPECIFIED
 6. COUNTERSINK 82 DEGREES APPROXIMATELY .03/.06 DEEP ALL DRILLED HOLES
 7. PARTS TO BE THOROUGHLY CLEANED TO REMOVE ALL OIL, GREASE, DIRT AND CHIPS
 8. PARTS TO BE IDENTIFIED BY PART NO., DASH NO., REVISION NO., SERIAL NO. TO BE CLEARLY MARKED ON THE PART ITSELF.

W.S. OCT 13 1999

ITEM NO.	QTY.	PART NO.	DESCRIPTION	MATERIAL
1	1	002-0212-263-D1	Left Support Block	SS1
2	1		Hex Hd Screw, 1/2-13 UNC-2A X 1.75 lg.	SS1
3	1		Flat Washer, 1/2"	SS1
4	1		5pc Hd Screw, 3/8-16 UNC-2A X 1.75 lg.	SS1

UNLESS OTHERWISE SPECIFIED		C/D OPERATED DRAWING	
DIMENSIONS IN MILLIMETERS		DO NOT MANUALLY UPDATE	
TOLERANCES		SCALE DRAWING	
FRACTIONS	DECIMALS	ANGLES	
1/16 = .0625	.001	1/16 = 1.57	
1/32 = .03125	.0005	1/32 = 3.14	
1/64 = .015625	.0001	1/64 = 6.28	

DRAWING NO.		002-0212-263-D1-1	
REV		D 1	
DATE		OCT 13 1999	
BY		W.S.	
CHKD			
APP'D			

HYTEC, INC	
PHENIX STATION 2 SOUTH	
SPIDER SUPPORT	
LEFT BRACKET ASSY	



PHENIX MuTr STATION 2 NORTH SPIDER INSTALLATION PROCEDURE

procedure name

PHENIX Procedure No. PP-2.5.5.4-19

Revision: A

Date: 4-22-02

Hand Processed Changes

<u>HPC No.</u>	<u>Date</u>	<u>Page Nos.</u>	<u>Initials</u>
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

Approvals

[Signature] 4/22/02
PHENIX S E & I Date

[Signature] 4/22/02
Cognizant Scientist/Engineer Date
/Activity Manager

[Signature] 4/22/02
PHENIX Safety Date

CA-D LIAISON Date

INTERNAL PROCEDURE

REVISION CONTROL SHEET

LETTER	DESCRIPTION	DATE	WRITTEN BY	APPROVED BY	CURRENT OVERSIGHT
A	First Issue	04/22/2002	n/a	P. Kroon, D. Lee, W. Lenz	n/a
RETIRED	Installation Complete	3/21/2007	n/a	D. Lynch, P. Giannotti, R. Pisani for PHENIX	D. Lynch

Station 2 North Spider Installation Procedure

1.0 Purpose and Scope

- 1.1 The purpose of this procedure is to provide direction for the rigging of the station 2 North support "spider". This structure locates all eight station 2 detectors in the North muon magnet. This procedure will provide detailed instructions for the safe installation of the support "spider" onto its mounting location off the back of the "teacup" and flanges on the bottom three lampshade panels.
Note that the weight for each half of the "spider" is 350 pounds.

2.0 Responsibilities

- 2.1 All operations shall be performed under the direction of the PHENIX experimental hall "person-in-charge", or their designee.
- 2.2 Due to the delicacy of this structure, and the critical alignment of its assembly in the magnet, this procedure and all relevant BNL safety guidelines must be strictly adhered to. In accordance with BNL policy, any individual may cease operations if they in any way feel unsafe or if they believe unsafe procedures are being followed, such a complaint shall be reviewed by the cognizant engineer, and if necessary, BNL ES&H service.

3.0 Prerequisites

- 3.1 Training: All personnel involved in this procedure shall have reviewed this procedure, and be fully knowledgeable about the way in which the support "spider" is assembled in the North magnet. A meeting will take place with all participants involved with this installation to review all aspects and answer any questions that any of the personnel may have.
- 3.2 All personnel involved with in this procedure shall have current BNL safety training requirements met to work in the PHEINX assembly hall, as part of Bldg. 1008. The crane operator must have a current BNL crane operation safety training.
- 3.3 All personnel involved in this procedure shall wear hardhats and safety shoes.

4.0 Precautions

- 4.1 The area where rigging operations will be performed shall be cordoned-off to all personnel except the "person in charge" and the technicians assigned to perform this procedure.
- 4.2 Some operations will require personnel to work in close proximity to suspended loads. Do not permit anyone to be positioned under the load.
- 4.3 Lift half spiders by the swivel eyes attached to the hub, or approved slings attached to the spider framing as required.

5.0 Equipment List

- 5.1 Appropriate slings for lifting 1000 pounds and shackles
- 5.2 Two-3/8 lifting swivel eyes (supplied by Kenny Jones) – Jergens part # 23408 rated for 1000 lbs. each.
- 5.3 Guide ropes.

6.0 Preparation

- 6.1 Mount 6 aluminum support brackets to top half of spider using 3/8-16 x 1-1/2 inch stainless steel hex head screw, (provided by Kenny Jones). Drawing number 126Y-267806, D2. On the lower half spider attach 6 aluminum brackets as called out on drawing 126Y-267806, D3. On the two splice tube weldments attach 4 aluminum brackets as indicated on drawing 126Y-267806, D6. The drawing of the overall assembly of the support spider is 126Y-267806, D1.
- 6.2 For each half spider install 3 3/8-16 x 2 inch long set screws where indicated on the hub on drawing 126Y-267806, D4-5.

7.0 Procedure

7.1 Bottom half spider.

- 7.1.1 The hub flange faces the upstream side of the notch in the piston or in the direction of station 1. Approximate weight 300 pounds.
- 7.1.2 After lowering the bottom half on to the wooden platform in the bottom of magnet, attach two slings to the junction of the outer radial spokes with the hub. See drawing 126Y-267806, D3. The slings will need to be long enough to go on either side of the magnet piston.
- 7.1.3 Move spoke portion of the half spider towards the magnet back plate with the hub facing the piston.
- 7.1.4 The six aluminum mounting blocks should be attached to the half spider using the 3/8-16 x 1.5 inch, hex head, stainless, and bolts. These bolts should not be completely tight. A 1/2-13 x 1.5 inch, socket head, stainless bolt is placed through the outer support bar and the aluminum block. This will be the fastener that mounts the half spider to the bottom three lampshade panels.
- 7.1.5 Lift the lower half of the spider into position in the piston notch, attach using the 1/2-13 socket head bolts, do not completely tighten until the top half of the spider and the splice tubes are attached.

7.2 Top half spider

- 7.2.1 The hub flange faces the upstream side of the piston notch, or station 1 side. See drawings 126Y-267806, sheets D1,2,3.
- 7.2.2 Attach two slings, of the proper load rating, to the junction of the outer support bars and central radial spoke (# 3 and 4 on drawing 126Y-267806, D2).
- 7.2.3 Attach guide ropes to the outer radial spokes to help position. Have all six aluminum mounting blocks attached to the outer support bars. Do not completely tighten.
- 7.2.4 Lift and lower the top half spider into place and attach to the teacup at the outside boundary. Attach upper half of spider to teacup flange using 6 1/2-13 x 1.5 inch long socket head screws. These are installed through the outer support bar – through the aluminum support brackets, into the teacup flange. Do not fully tighten until spider is fully assembled.

7.3 Splice tube weldments




- 7.3.1 Attach the two splice tube weldment assemblies as shown in the overall spider assembly drawing 126Y-267806, D1. The weldment tubes are shown on 126Y-267806, D6. These tubes bolt to the two spider halves; each uses 4 bolts with washers and nuts.
- 7.3.2 Prior to alignment, it is possible to use the 6 – 3/6-16 x 3 inch long screws that pass through the spider hub, to help fine position the spider assembly to the teacup. Tighten all bolts.

8.0 Alignment

8.1 Survey the spider assembly.

- 8.1.1 There are 32 paste on targets around the outer support bars and weldment bars, two per aluminum mounting block. They are placed on the stainless inserts that have been machined parallel to the tube. The surfaces of these inserts will set the plane for the spider. There are a couple of paste on targets close to the spider hub. The aluminum spider mounting blocks have been machined to give a designed surface of the back of the teacup at a PHENIX Z value of 3,400 mm from the IP. The plane for the outer 32 targets should be within a plane that is better then 1mm in Z.

LOOKING (PHENIX) NORTH, SPIDER SUPPORT BLOCK 44's



SCALE .025

SCALE .10

NOV 09 2001

ALL DIMENSIONS IN MILLIMETERS

PARTS LIST

ITEM NO.	QTY	DWG. NO.	DESCRIPTION
1	1	002-0212-360-02	TOP FRAME SUB-ASSEMBLY
2	1	002-0212-360-03	BOTTOM FRAME SUB-ASSEMBLY
3	2	002-0212-360-06	SPLICE TUBE WELDMENT
4	8	002-0212-360-010	REAR OCTANT STABILIZER
5	16	002-0212-360-011	SUPPORT BRACKET

ITEM NO.	QTY	DWG. NO.	DESCRIPTION
1	1	002-0212-360-02	TOP FRAME SUB-ASSEMBLY
2	1	002-0212-360-03	BOTTOM FRAME SUB-ASSEMBLY
3	2	002-0212-360-06	SPLICE TUBE WELDMENT
4	8	002-0212-360-010	REAR OCTANT STABILIZER
5	16	002-0212-360-011	SUPPORT BRACKET

Los Alamos

Los Alamos National Laboratory

Los Alamos, New Mexico 87545

STATION 2 NORTH
SPIDER SUPPORT
RING ASSEMBLY

PHENIX DRAWING NO. 002-0212-360-01


DATE: 0.08.01.25

SCALE: 1/16

126V-287806 D

NOTES: UNLESS OTHERWISE SPECIFIED

- 1. DIMENSIONS AND TOLERANCES PER ANSI Y14.5M-1994
- 2. SURFACE TEXTURE PER ANSI/ASME B.46.1-1985
- 3. UNLESS OTHERWISE SPECIFIED, ALL DIMENSIONS ARE TO A MAX. OF .4
- 4. ALL INSIDE CORNERS AND BEVELS TO BE R4
- 5. COUNTERSINK 82 DEGREES APPROXIMATELY .8 DEEP ALL DRILLED HOLES
- 6. PARTS TO BE THOROUGHLY CLEANED TO REMOVE ALL OIL, GREASE, DIRT AND CHIPS



US DEC 17 2001

ALL DIMENSIONS IN MILLIMETERS

ITEM NO.	QTY.	UNG. NO.	DESCRIPTION
1	1	002-0212-380-04	UPPER SUPPORT RING
2	2	002-0212-380-07	OUTER RADIAL SHAFT
3	2	002-0212-380-08	CENTRAL RADIAL SHAFT
4	3	002-0212-380-08	OUTER RADIAL SHAFT
			INITIAL RELEASE
			ORIGINAL ISSUE
			WALT
			WALT

DETAIL B

NOTES: UNLESS OTHERWISE SPECIFIED

1. DIMENSIONS AND TOLERANCES PER ANAS 1 Y14.5M-1994
2. SURFACE TEXTURE PER ANAS 1 Y14.5M-1994
3. REMOVE ALL BURRS AND BREAK SHARP EDGES TO A MAX. OF .4
4. ALL INTERNAL CORNERS TO BE R4 RADIUS MAX
5. COUNTERSINK 82 DEGREES ALL TAPPED HOLES TO MAJOR DIAMETER
6. COUNTERSINK 82 DEGREES APPROXIMATELY 1/2 DEEP ALL DRILLED HOLES
7. PARTS TO BE THOROUGHLY CLEANED TO REMOVE ALL OIL, GREASE, DIRT AND CHIPS

DETAIL A

SCALE .25

Los Alamos

Los Alamos National Laboratory

Los Alamos, New Mexico 87545

STATION 2 NORTH

SUPPLIER SPIDER

UPPER ASSEMBLY


PRELIM DRAWING NO. 002-0212-380-02

DATE: 10/01/94

BY: J. J. J. J.

1/10

126Y-267806 D 2



W 5 DEC 07 2001

ALL DIMENSIONS IN MILLIMETERS

ITEM NO.	QTY.	DWG. NO.	DESCRIPTION
1	1	002-02120360-05	LOWER SUPPORT RING
2	2	002-02120360-07	OUTER RADIAL SPOKE
3	2	002-02120360-08	CENTRAL RADIAL SPOKE
4	3	002-02120360-09	OUTER SUPPORT BARS

ITEM NO.	QTY.	DWG. NO.	DESCRIPTION
1	1	002-02120360-05	LOWER SUPPORT RING
2	2	002-02120360-07	OUTER RADIAL SPOKE
3	2	002-02120360-08	CENTRAL RADIAL SPOKE
4	3	002-02120360-09	OUTER SUPPORT BARS

ITEM NO.	QTY.	DWG. NO.	DESCRIPTION
1	1	002-02120360-05	LOWER SUPPORT RING
2	2	002-02120360-07	OUTER RADIAL SPOKE
3	2	002-02120360-08	CENTRAL RADIAL SPOKE
4	3	002-02120360-09	OUTER SUPPORT BARS

ITEM NO.	QTY.	DWG. NO.	DESCRIPTION
1	1	002-02120360-05	LOWER SUPPORT RING
2	2	002-02120360-07	OUTER RADIAL SPOKE
3	2	002-02120360-08	CENTRAL RADIAL SPOKE
4	3	002-02120360-09	OUTER SUPPORT BARS

ITEM NO.	QTY.	DWG. NO.	DESCRIPTION
1	1	002-02120360-05	LOWER SUPPORT RING
2	2	002-02120360-07	OUTER RADIAL SPOKE
3	2	002-02120360-08	CENTRAL RADIAL SPOKE
4	3	002-02120360-09	OUTER SUPPORT BARS

ITEM NO.	QTY.	DWG. NO.	DESCRIPTION
1	1	002-02120360-05	LOWER SUPPORT RING
2	2	002-02120360-07	OUTER RADIAL SPOKE
3	2	002-02120360-08	CENTRAL RADIAL SPOKE
4	3	002-02120360-09	OUTER SUPPORT BARS

ITEM NO.	QTY.	DWG. NO.	DESCRIPTION
1	1	002-02120360-05	LOWER SUPPORT RING
2	2	002-02120360-07	OUTER RADIAL SPOKE
3	2	002-02120360-08	CENTRAL RADIAL SPOKE
4	3	002-02120360-09	OUTER SUPPORT BARS

ITEM NO.	QTY.	DWG. NO.	DESCRIPTION
1	1	002-02120360-05	LOWER SUPPORT RING
2	2	002-02120360-07	OUTER RADIAL SPOKE
3	2	002-02120360-08	CENTRAL RADIAL SPOKE
4	3	002-02120360-09	OUTER SUPPORT BARS

Los Alamos

Los Alamos National Laboratory
Los Alamos, New Mexico 87545

STATION 2 NORTH
SUPPORT SPIDER
LOWER ASSEMBLY

PRELIM DRAWING NO. 002-0212-000103

DATE: 10/01/95


SCALE: 1/10

126V-267806 D 3

DETAIL OF END MOUNT PLATE, FROM SHEET D6

NOTES: UNLESS OTHERWISE SPECIFIED

1. DIMENSIONS AND TOLERANCES PER ANSI Y14.5M-1994
2. SURFACE TEXTURE PER ANI/ASME B 46.1-1985
3. REMOVE ALL BURRS AND BREAK SHARP EDGES TO A MAX. OF .4
4. ALL INSIDE CORNERS TO BE .4 RADIUS MAX.
5. COUNTERSINK 82 DEGREES ALL TAPPED HOLES TO MAJOR DIAMETER
6. COUNTERSINK 82 DEGREES APPROXIMATELY .8 DEEP ALL DRILLED HOLES
7. PARTS TO BE THOROUGHLY CLEANED TO REMOVE ALL OIL, GREASE, DIRT AND CHIPS



Ø 13/32" THRU, 2X

(9.52)

NOV 09 2001

ALL DIMENSIONS IN MILLIMETERS

CLASSIFICATION:		PART:		TITLE BLOCK:		INITIAL RELEASE		11/01		WALT	
DRAWING:	SIGNATURE	DATE	GROUP	REV	CLASS	REVISIONS	ORIGINAL	ISSUE	DATE	CHECKED	APPROVED
ORIG	WALT	11/01	P-25								
DRAWN											
CHECKED											
PROJ ENGR											
APPROVED											
RELEASED											

LOS ALAMOS		STATION 2 NORTH	
LOS ALAMOS NATIONAL LABORATORY		SUPPORT SPIDER	
LOS ALAMOS, NEW MEXICO, 87545		SPLICE TUBE END PLATE	
TOLERANCE-UNLESS OTHERWISE NOTED		PHENIX DRAWING NO. 002-0212-806-B8A	
±.05	0.05 ±.05	ANG ±.25	SCALE
±.05	0.0005 ±	FIN ±.2	1:1
TOTAL SHEETS		DRAWING NO.	
1		126Y-267806 B	
SIZE		NO.	
B		6A	

MAT'L: SST 304, MAKE 2



**PHENIX MuTr STATION 2 NORTH INSTALLATION
PROCEDURE**

procedure name

PHENIX Procedure No. PP-2.5.5.4-20

Revision: A

Date: 4-22-02

Hand Processed Changes

<u>HPC No.</u>	<u>Date</u>	<u>Page Nos.</u>	<u>Initials</u>
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

Approvals

Peter Krause 4/24/02
PHENIX S E & I Date

Darrell M. Lee
Cognizant Scientist/Engineer Date
/Activity Manager

Willie H. King 4/24/02
PHENIX Safety Date

Charles Pearson 4/24/02
CA-D LIAISON Date

REVISION CONTROL SHEET

LETTER	DESCRIPTION	DATE	WRITTEN BY	APPROVED BY	CURRENT OVERSIGHT
A	First Issue	04/22/2002	n/a	P. Kroon, D. Lee, W. Lenz, C. Pearson	n/a
RETIRED	Installation Complete	3/21/2007	n/a	D. Lynch, P. Giannotti, R. Pisani for PHENIX	D. Lynch

Station 2 North Installation Procedure

1.0 Purpose and Scope

- 1.1 The purpose of this procedure is to provide direction for the rigging of the station 2 North octants. This procedure will provide detailed instructions for the safe installation of the octants onto its mounting location on the back of the "spider". Note that the weight for each octant is 325 lbs.

2.0 Responsibilities

- 2.1 All operations shall be performed under the direction of the PHENIX experimental hall "person-in-charge", or their designee.
- 2.2 Due to the delicacy of this structure, and the critical alignment of its assembly in the magnet, this procedure and all relevant BNL safety guidelines must be strictly adhered to. In accordance with BNL policy, any individual may cease operations if they in any way feel unsafe or if they believe unsafe procedures are being followed, such a complaint shall be reviewed by the cognizant engineer, and if necessary, BNL ES&H service.

3.0 Prerequisites

- 3.1 Training: All personnel involved in this procedure shall have reviewed this procedure, and be fully knowledgeable about the way in which the octant is mounted in the North magnet. A meeting will take place with all participants involved with this installation to review all aspects and answer any questions that any of the personnel may have. All personnel shall sign acknowledgement sheets to this affect.
- 3.2 All personnel involved with in this procedure shall have current BNL safety training requirements met to work in the PHENIX experimental hall, Bldg. 1008. The crane operator must have a current BNL crane operation safety training.
- 3.3 All personnel involved in this procedure shall wear hardhats and safety shoes.

4.0 Precautions

- 4.1 The area where rigging operations will be performed shall be cordoned-off to all personnel except the "person in charge" and the technicians assigned to perform this procedure.
- 4.2 Some operations will require personnel to work in close proximity to suspended loads. Do not permit anyone to be positioned under the load.
- 4.3 Lift the octants with the commercial lifting fixture only and only with the protective covers in place on the octant.

5.0 Equipment List

- 5.1 Appropriate ANVER lifting fixture.
- 5.2 "C" fixture, Dwg. No. 002-0212-610-1A.
- 5.3 Guide ropes.
- 5.4 Shackles

6.0 Preparation

- 6.1 Support "spider" in place.

- 6.2 Stainless threaded rods in place on the "spider" where the octant is to be placed. No other threaded rods in place on spider except where octant is already installed.

7.0 Procedure

7.1 Front octants.(smaller octants)

- 7.1.1 The frame side with the machined surface cutout faces downstream. Installation proceeds from the bottom of the spider to the top at every other location beginning at 6:00 o'clock and proceeding in order 6:00,3:00,9:00,12:00.
- 7.1.2 **FIRST OCTANT ONLY _ 6:00 position**
 - 7.1.2.1 Attach "C" fixture to the crane hook and attach the ANVER lifting fixture to the "C" fixture.
- 7.1.3 Attach the ANVER lifting fixture to the octant in the horizontal position following the manufacturer's instructions and with the fixtures provided. Lift the octant and tilt the octant to a vertical position.
- 7.1.4 Rotate the octant to the orientation in the "spider".
- 7.1.5 Attach guide ropes to the octant.
- 7.1.6 **First Octant Only**
 - 7.1.6.1 Lift and lower the octant in place downstream of the spider, to allow possible rotation of the octant to get into position under the piston. Once the octant is directly under the piston move upstream and attach to the "spider" at the outside boundary. Place temporary nuts and spacers on the side threaded rod, using guide ropes as needed to stabilize the octant
- 7.1.7 **Remaining octants**
 - 7.1.7.1 No "C" fixture needed. Lift and lower the octant into place. Attach the spider to the outside assembly and place temporary nuts and spacers on the threaded rod on the sides.
- 7.1.8 Remove aluminum plates on the upstream side of the octants.
- 7.1.9 Install alignment lenses.

7.2 Rear Octants.

- 7.2.1 The frame side with the machined surface for the lens blocks faces downstream. Installation proceeds from the bottom of the spider to the top at every other location beginning at 4:30 o'clock and proceeding in order 4:30,7:30,1:30,10:30.
- 7.2.2 Attach the ANVER lifting fixture to the octant in the horizontal position following the manufacturers instructions. Lift the octant and tilt the octant to a vertical position.
- 7.2.3 Rotate the octant to the orientation in the "spider".
- 7.2.4 Attach guide ropes to the octant.
- 7.2.5 Remove temporary nuts on adjacent octants on the sides.
- 7.2.6 Attach 2 stabilizer brackets to the outside cross member on the spider, drawing number 002-0212-806 D10.
- 7.2.7 Remove protective aluminum cover on upstream side of octant.
- 7.2.8 Lift and lower the octant into place and attach to the stabilizer brackets at the outside boundary. Place nuts and washers on the side threaded rods and torque to 20 ft-lbs. Use guide ropes as needed to stabilize the octant until nuts are secured.
- 7.2.9 Install alignment lenses.

7.3 Remove downstream protective covers as the FEE system is installed.

8.0 Alignment

8.1 Survey the octants and fine tune locations of the octants beginning at the bottom and working towards the top from the downstream side. Check all mounting nuts for torque of 20 ft-lb.



ALL DIMENSIONS IN MILLIMETERS		
ITEM NO.	QTY.	DESCRIPTION
1	1	SQUARE TUBING 2" X 2" X .120 WALL
2	1	PLATE
3	1	ALUMINUM
		MATERIAL
		SST-304
		SST-304

	A	INITIAL RELEASE	11/01	WALT
		ORIGINAL ISSUE		
		REVISIONS	SITE	STATUS
	OTHER DATE			APPROVE

Los Alamos

Los Alamos National Laboratory
Los Alamos, New Mexico 87545

	SUPPORT SPIDER
	REAR OCTANT STABILIZER

SIGNATURE	DATE	GROUP
WALF	11/01	P-25
DESIGNED BY		
CHECKED BY		
DRAWN BY		
SCALE		
PROJECT NO.		
11		
1267-267808		
010		

NOTES: UNLESS OTHERWISE SPECIFIED

1. DIMENSIONS AND TOLERANCES PER ANSI Y14.5M-1984
2. SURFACE TEXTURE PER ANSI/ASME B 46.1-1985
3. REMOVE ALL BURRS AND BREAK SHARP EDGES TO A MAX. OF .4
4. ALL INSIDE CORNERS TO BE .4 RADIUS MAX.
5. COUNTERSINK 82 DEGREES ALL TAPPED HOLES TO MAJOR DIAMETER
6. COUNTERSINK 82 DEGREES APPROXIMATELY .8 DEEP ALL DRILLED HOLES
7. PARTS TO BE THOROUGHLY CLEANED TO REMOVE ALL OIL, GREASE, DIRT



**PHENIX MuTr STATION 3 NORTH INSTALLATION
PROCEDURE**

procedure name

PHENIX Procedure No. PP-2.5.5.4-21

Revision: A

Date: 4-23-02

Hand Processed Changes

<u>HPC No.</u>	<u>Date</u>	<u>Page Nos.</u>	<u>Initials</u>
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

Approvals

Victor Kwan 4/30/02
PHENIX S E & I Date

David M Lee 14 May 02
Cognizant Scientist/Engineer Date
/Activity Manager

William Ray 4/30/02
PHENIX Safety Date

Charles Dean 5/14/2002
CA-D LIAISON Date

REVISION CONTROL SHEET

LETTER	DESCRIPTION	DATE	WRITTEN BY	APPROVED BY	CURRENT OVERSIGHT
A	First Issue	04/23/2002	n/a	P. Kroon, D. Lee, W. Lenz, C. Pearson	n/a
RETIRED	Installation Complete	3/21/2007	n/a	D. Lynch, P. Giannotti, R. Pisani for PHENIX	D. Lynch

Station 3 North Installation Procedure

1.0 Purpose and Scope

- 1.1 The purpose of this procedure is to provide direction for the rigging of the station 3 North octants. This procedure provides detailed instructions for the safe installation of the octants onto their mounting locations on the back plate of the north muon magnet. Note that the weight for each octant is 600 lbs.

2.0 Responsibilities

- 2.1 All operations shall be performed under the direction of the PHENIX experimental hall "person-in-charge", or their designee.
- 2.2 Due to the delicacy of this structure, and the critical alignment of its assembly in the magnet, this procedure and all relevant BNL safety guidelines must be strictly adhered to. In accordance with BNL policy, any individual may cease operations if they in any way feel unsafe or if they believe unsafe procedures are being followed, such a complaint shall be reviewed by the cognizant engineer, and if necessary, BNL ES&H service.

3.0 Prerequisites

- 3.1 Training: All personnel involved in this procedure shall have reviewed this procedure, and be fully knowledgeable about the way in which the octant is mounted in the North magnet. A meeting will take place with all participants involved with this installation to review all aspects and answer any questions that any of the personnel may have.
- 3.2 All personnel involved with in this procedure shall have current BNL safety training requirements met to work in the PHENIX experimental hall, Bldg. 1008. The crane operator must have a current BNL crane operation safety training.
- 3.3 All personnel involved in this procedure shall wear hardhats and safety shoes.

4.0 Precautions

- 4.1 The area where rigging operations will be performed shall be cordoned-off to all personnel except the "person in charge" and the technicians assigned to perform this procedure.
- 4.2 Some operations will require personnel to work in close proximity to suspended loads. Do not permit anyone to be positioned under the load.
- 4.3 Lift the octants with the commercial lifting fixture only.

5.0 Equipment List

- 5.1 Appropriate ANVER lifting fixture.
- 5.2 "C" fixture, 1200 Lb. Capacity.
- 5.3 Guide ropes.
- 5.4 Shackles

6.0 Preparation


- 6.1 Kinematic mounts pre-set. See drawing 002-0212-524 B1A, B2A for kinematic mount preset adjustments.
- 6.2 Magnet hoses tested and leak tight.
- 6.3 All kinematic mounts attached to magnet back plate as shown in drawing 002-0212-610 D11a,D12 and 002-0212-524 B1,B2,B3

7.0 Procedure

- 7.1 The side with the kinematic mounts face magnet back plate. Installation proceeds from the bottom of the magnet to the top beginning at 6:00 o'clock and proceeding in order 6:00,4:30,7:30,3:00,9:00,1:30,10:30,12:00.
- 7.2 FIRST OCTANT ONLY _ 6:00 position
 - 7.2.1 Attach "C" fixture to the crane hook and attach the ANVER vacuum lifting fixture to the "C" fixture using a shackle.
- 7.3 Attach the ANVER lifting fixture to the octant in the horizontal position following the manufacturer's instructions. Lift the octant only after the vacuum pump has turned off. Rotate the octant to a vertical position.
 - 7.3.1 For the First octant at 6:00 o'clock the octant may need to be in an intermediate position between horizontal and vertical.
- 7.4 Rotate the octant to the proper orientation.
 - 7.4.1 For the First octant at 6:00 o'clock rotate the octant to an intermediate position as it is lowered and then rotate the to the 6:00 o'clock position.
- 7.5 Attach guide ropes to the octant.
- 7.6 Lift and lower the octant into place on the kinematic mounts. Use guide ropes to stabilize the octant during installation.
- 7.7 After all octants are installed on the magnet backplate, install alignment system cameras and mounts.

8.0 Alignment


- 8.1 Survey the octants.
- 8.2 See projected survey points on drawings 002-0212-466 D1-D8




ALL DIMENSIONS IN MILLIMETERS

05 JUL 27 2007

Los Alamos		NORTH ARN, STATION 3	
Los Alamos National Laboratory		OCTANT # 2	
Los Alamos, New Mexico 87545		SURVEY POINTS	
DATE	7/27/07	TIME	14:00
BY	J. L. ...	BY	J. L. ...
CHECKED	J. L. ...	CHECKED	J. L. ...
APPROVED	J. L. ...	APPROVED	J. L. ...
PROJECT NO. 003-012-100		PROJECT NO. 003-012-100	
PROJECT NAME		PROJECT NAME	
PROJECT LOCATION		PROJECT LOCATION	
PROJECT CONTACT		PROJECT CONTACT	
PROJECT PHONE		PROJECT PHONE	
PROJECT FAX		PROJECT FAX	
PROJECT E-MAIL		PROJECT E-MAIL	
PROJECT URL		PROJECT URL	
PROJECT STATUS		PROJECT STATUS	
PROJECT COMMENTS		PROJECT COMMENTS	






VIEW LOOKING NORTH


35 JUL 27 2009

ALL DIMENSIONS IN MILLIMETERS

Los Alamos Los Alamos National Laboratory Los Alamos, New Mexico 87545		INITIAL RELEASE ORIGINAL 1964		DATE 7/21		BY B.L.T.	
PROJECT NO. NORTH SRM, STATION 3 OCCUPANT # 5 SURVEY POINTS		DRAWING NO. 005-0312-400		SCALE 1:1		DATE 1287-2878110 5	
TITLE NORTH SRM, STATION 3 OCCUPANT # 5 SURVEY POINTS		DRAWING NO. 005-0312-400		SCALE 1:1		DATE 1287-2878110 5	



Los Alamos Los Alamos National Laboratory Los Alamos, New Mexico 87545		INITIAL RELEASE ORIGINAL ISSUE		7/01		W/LT	
NORTH ARM, STATION 3 OCTANT # 6 SURVEY POINTS		DATE 7/01		7/01		7/01	
DRAWN BY 128V-267811 D 6		CHECKED BY 128V-267811 D 6		DATE 7/01		7/01	



ALL DIMENSIONS IN MILLIMETERS


5 JUL 27 2004

Los Alamos Los Alamos National Laboratory 701 Los Alamos, New Mexico 87545		DRAWING NO. 000-0012-000 TITLE: NORTH AREA STATION 3 SURVEY POINTS DATE: 7/20/04 BY: [Signature] CHECKED: [Signature] APPROVED: [Signature]	
STRUCTURE WALL 7/20/04 1-25	DATE 7/20/04	SCALE 1"=25'	SHEET NO. 1

ITEM NUMBER	RECD	DESCRIPTION
----------------	------	-------------

5/8-11UNC NUT, SST
 SWIVEL SCREW CLAMP
 CARR LANE #CL-69-SSC
 5/8-11UNC X 5.22" LG,
 5/16" HEX DRIVE

NOTE
 1. ORIENTATION OF 3/8 THR. ROD
 MAY VARY.



SUPPORT CONE ASSY
 8 RECD

X & Y ADJUSTMENT


U.S. AUG 20 1999

CLASSIFICATION		PART		TITLE BLOCK		REV		CLASS		ORIGINAL ISSUE		DATE		CHANGED		CHECKED		APPROVED	
DRAWING		SIGNATURE		DATE		GROUP		REV		REVISIONS		DATE		CHANGED		CHECKED		APPROVED	
ORIG		CLARK		8/99		P-25													
DRAWN		CLARK		8/99		P-25													
CHECKED																			
PROD ENG																			
APPROVED																			
RELEASED																			

LOS ALAMOS		TITLE		PHENIX MUON KINEMATIC MOUNT SUPPORT CONE ASSY	
LOS ALAMOS NATIONAL LABORATORY		REV		DATE	
LOS ALAMOS, NEW MEXICO, 87545		CHANGED		BY	
TOLERANCE - (UNLESS OTHERWISE NOTED)		CHECKED		BY	
X's 0.001" ±		APPROVED		DATE	
Y's 0.0001" ±		RELEASED		DATE	
Z's 0.0001" ±		FIN		DATE	
SCALE		TOTAL SHEETS		DRAWING NO.	
1:1		126Y-267771		B	
SIZE		NO.		1	

ITEM	MANAGER	DESCRIPTION
MANAGER	RECD	

NOTE
1. ORIENTATION OF 3/8 THR. ROD
MAY VARY.



SUPPORT SLIDE ASSY
8 RECD

Y ADJUSTMENT
X FREEDOM

4.5, AUG 20 1999

CLASSIFICATION	PART	TITLE BLOCK	REV	DATE	GROUP	ORIGINAL	ISSUE	DATE	CHANGED	CHECKED	APPROVED
ORIG	SIGNATURE	DATE	GROUP								
ORIG	CLARK	7-99	P-25								
CHECKED											
PROJ ENGR											
APPROVED											
RELEASED											

LOS ALAMOS

LOS ALAMOS NATIONAL LABORATORY
LOS ALAMOS, NEW MEXICO, 87545

TOLEANCE - UNLESS OTHERWISE NOTED

X+.0000 -0.0000
X+.0000 -0.0000

PHENIX MUON
KINEMATIC MOUNT
SUPPORT SLIDE ASSY



PHENIX DRAWING NO. 002-0212-524

SCALE TOTAL
N/A SHEETS 126Y-267771 B 2

SUPPORT STOP ASSY
8 REOD
Z ADJUSTMENT
Y FREEDOM
X FREEDOM

CLASSIFICATION:		ORIGINAL ISSUE					
DRAWING NO.	PART	TITLE BLOCK	REV	CLASS	REVISIONS	DATE	DRAWN BY
SIGNATURE	DATE	GROUP	REV	REVIEW			
ORIG			LOS ALAMOS				
DRAWN	CLARK	B-99	LOS ALAMOS NATIONAL LABORATORY				
CHECKED		P-25	LOS ALAMOS, NEW MEXICO, 87545				
PROD ENGR			TOLERANCE (UNLESS OTHERWISE NOTED)				
APPROVED			X 1/8 0.125 1/8 1/16 1/32 1/64 1/128 1/256 1/512 1/1024 1/2048 1/4096 1/8192 1/16384 1/32768 1/65536 1/131072 1/262144 1/524288 1/1048576 1/2097152 1/4194304 1/8388608 1/16777216 1/33554432 1/67108864 1/134217728 1/268435456 1/536870912 1/1073741824 1/2147483648 1/4294967296 1/8589934592 1/17179869184 1/34359738368 1/68719476736 1/137438953472 1/274877906944 1/549755813888 1/1099511627776 1/2199023255552 1/4398046511104 1/8796093022208 1/17592186044416 1/35184372088832 1/70368744177664 1/140737488355328 1/281474976710656 1/562949953421312 1/1125899906842624 1/2251799813685248 1/4503599627370496 1/9007199254740992 1/18014398509481984 1/36028797018963968 1/72057594037927936 1/144115188075855872 1/288230376151711744 1/576460752303423488 1/1152921504606846976 1/2305843009213693952 1/4611686018427387904 1/9223372036854775808 1/18446744073709551616 1/36893488147419103232 1/73786976294838206464 1/147573952589676412928 1/295147905179352825856 1/590295810358705651712 1/1180591620717411303424 1/2361183241434822606848 1/4722366482869645213696 1/9444732965739290427392 1/18889465931478580854784 1/37778931862957161709568 1/75557863725914323419136 1/151115727451828646838272 1/302231454903657293676544 1/604462909807314587353088 1/1208925819614629174706176 1/2417851639229258349412352 1/4835703278458516698824704 1/9671406556917033397649408 1/19342813113834066795298816 1/38685626227668133590597632 1/77371252455336267181195264 1/154742504910672534362390528 1/309485009821345068724781056 1/618970019642690137449562112 1/1237940039285380274899124224 1/2475880078570760549798248448 1/4951760157141521099596496896 1/9903520314283042199192993792 1/19807040628566084398385987584 1/39614081257132168796771975168 1/79228162514264337593543950336 1/158456325028528675187087900672 1/316912650057057350374175801344 1/633825300114114700748351602688 1/1267650600228229401496703205376 1/2535301200456458802993406410752 1/5070602400912917605986812821504 1/10141204801825835211973625643008 1/20282409603651670423947251286016 1/40564819207303340847894502572032 1/81129638414606681695789005144064 1/162259276829213363391578010288128 1/324518553658426726783156020576256 1/649037107316853453566312041152512 1/1298074214633706907132624082305024 1/2596148429267413814265248164610048 1/5192296858534827628530496329220096 1/10384593717069655257060992658440192 1/20769187434139310514121985316880384 1/41538374868278621028243970633760768 1/83076749736557242056487941267521536 1/166153499473114484112975882535043072 1/332306998946228968225951765070086144 1/664613997892457936451903530140172288 1/1329227995784915872903807060280344576 1/2658455991569831745807614120560689152 1/5316911983139663491615228241121378304 1/10633823966279326983230456482242756608 1/21267647932558653966460912964485513216 1/42535295865117307932921825928971026432 1/85070591730234615865843651857942052864 1/170141183460469231731687303715884105728 1/340282366920938463463374607431768211456 1/680564733841876926926749214863536422912 1/1361129467683753853853498429727072845824 1/2722258935367507707706996859454145691536 1/5444517870735015415413993718908291383072 1/10889035741470030830827987437816582766144 1/21778071482940061661655974875633165532288 1/43556142965880123323311949751266331064576 1/87112285931760246646623899502532662129152 1/17422457186352049329324779900506524255808 1/34844914372704098658649559801013048511616 1/69689828745408197317299119602026097023232 1/139379657490816394634598239204052194046464 1/278759314981632789269196478408104388092928 1/557518629963265578538392956816208776185856 1/111503725992653115707678591363241553371136 1/223007451985306231415357182726483106742272 1/446014903970612462830714365452966213484544 1/8920298079412249256				

ITEM NUMBER		REVISION		DESCRIPTION	





NOMINAL SETTING FOR KINEMATIC MOUNT SUPPORT SLIDE ASSY

WJ APR 17 2008

CLASSIFICATION:		PART:		TITLE BLOCK:		REV		CLASS		ORIGINAL ISSUE		DATE		CHECKED		APPROVED	
DRAWING:		SIGNATURE:		DATE:		GROUP:		REV		REVISED		DATE		CHECKED		APPROVED	
ORIG:		CLARK		4/00		P-25		LOS ALAMOS		LOS ALAMOS NATIONAL LABORATORY		LOS ALAMOS, NEW MEXICO, 87545		PHENIX MUON		KINEMATIC MOUNT	
CHECKED:								TOLERANCE - (UNLESS OTHERWISE NOTED)		SCALE		TOTAL SHEETS		DRAWING NO.		SIZE	
PROD ENG:								X ₁ ± 0.0005		X ₂ ± 0.0005		X ₃ ± 0.0005		X ₄ ± 0.0005		X ₅ ± 0.0005	
APPROVED:								X ₆ ± 0.0005		X ₇ ± 0.0005		X ₈ ± 0.0005		X ₉ ± 0.0005		X ₁₀ ± 0.0005	
RELEASED:								X ₁₁ ± 0.0005		X ₁₂ ± 0.0005		X ₁₃ ± 0.0005		X ₁₄ ± 0.0005		X ₁₅ ± 0.0005	

ITEM	NUMBER	DESCRIPTION
1	1000	




ANGULAR POS'N OF THESE BOLTS
WILL VARY BY PANEL LOCATION

NOMINAL SETTING FOR KINEMATIC MOUNT SUPPORT CONE ASSY

CLASSIFICATION:		TITLE BLOCK:		REV		ORIGINAL		ISSUE		DATE		CHANGED		CHECKED		APPROVED	
DESIGN	PART	SIGNATURE	DATE	GROUP	REV	CLASS	REVISIONS	DATE	CHANGED	BY	DATE	CHANGED	BY	DATE	CHANGED	BY	DATE
ORIG																	
DRWN	CLARK		4/00	P-25													
CHECKED																	
PROJ ENGR																	
APPROVED																	
RELEASED																	

5 APR 17 2000

LOS ALAMOS		TITLE		PHENIX MUON		KINEMATIC MOUNT		SUPPORT CONE ASSY	
LOS ALAMOS NATIONAL LABORATORY		LOS ALAMOS, NEW MEXICO, 87545		PHENIX DRIVING NO. 002-0212-524		SCALE		TOTAL SHEETS	
TOLERANCE - (UNLESS OTHERWISE NOTED)		X1/8 0.001 0.0005 0.0001		FIN		.5		126Y-267771B 1A	



ALL DIMENSIONS IN MILLIMETERS

10/17/00 U.S.

Los Alamos Los Alamos National Laboratory Los Alamos, New Mexico 87545		PROJECT MAJOR NORTH WAREHOUSE STATION 3 KINEMATIC MAJOR FIELDS	
DATE JUN 10-00	BY P-25	SCALE 1:250	PROJECT NO. 002-0212-010-12
DESIGNED BY JUN 10-00	CHECKED BY P-25	DATE JUN 10-00	PROJECT NO. 002-0212-010-12
PROJECT NO. 002-0212-010-12	PROJECT NO. 002-0212-010-12	PROJECT NO. 002-0212-010-12	PROJECT NO. 002-0212-010-12

Scaffold Safety Checklist

Project & Scaffold:	Job #	WO #:
Date of Inspection: _____ Competent Person(s): _____ Date Scaffold is complete: _____		

[illegible]